RFQ Reference: 2905KMID2023ISA	Date: 25 May 2023
--------------------------------	-------------------

**Subject:** Supply, Installation, Testing & Commissioning (SITC) of equipment and instruments for setting up the STAR Centre in Somalia including one year Comprehensive Maintenance Contract (CMC).

## **SECTION 1: REQUEST FOR QUOTATION (RFQ)**

ISA kindly requests your quotation for the provision of goods, works and/or services as detailed in Annex 1 of this RFQ.

This Request for Quotation comprises the following documents:

Section 1: This Request Letter

Section 2: RFQ Instructions and Data

Annex 1: Schedule of Requirements

Annex 2: Quotation Submission Form

Annex 3: Technical and Financial Offer

Annex 4: Description of solar trainer and demonstrator

When preparing your quotation, please be guided by the RFQ Instructions and Data. Please note that quotations must be submitted using Annex 2: Quotation Submission Form and Annex 3 Technical and Financial Offer, by the method and by the date and time indicated in Section 2. It is your responsibility to ensure that your quotation is submitted on or before the deadline. Quotations received after the submission deadline, for whatever reason, will not be considered for evaluation.

The ISA recognizes the importance of valuing diversity and promoting inclusion in all our work programs and partnerships. The ISA highly values engaging with organizations and/or teams that reflect its geographical and diverse nature.

Thank you and we look forward to receiving your quotations.

Issued by:	
Signature:	
Name:	Procurement Unit
Date:	25/05/2023

## **SECTION 2: RFQ INSTRUCTIONS AND DATA**

Introduction	Bidders shall adhere to all the requirements of this RFQ, including any amendments made in writing by ISA. This RFQ is conducted in accordance with the ISA Financial Regulations and Procedures and ISA Procurement Manual  Any Bid submitted will be regarded as an offer by the Bidder and does not constitute or imply the acceptance of the Bid by ISA. ISA is under no obligation to award a contract to any Bidder as a result of this RFQ.  ISA reserves the right to cancel the procurement process at any stage without any liability of any
	kind for ISA, upon notice to the bidders or publication of cancellation notice on ISA website
Deadline for the Submission of Quotation	15.06.2023 by 1900 HRS IST  If any doubt exists as to the time zone in which the quotation should be submitted, refer to <a href="http://www.timeanddate.com/worldclock/">http://www.timeanddate.com/worldclock/</a> .
	For eTendering submission - as indicated in eTendering system. Note that system time zone is in EST/EDT (New York) time zone.
Method of Submission	Quotations must be submitted as follows:  □ E-tendering  ☑ Dedicated Email Address  □ Courier / Hand delivery  □ Other Click or tap here to enter text.  Bid submission address: procurement@isolaralliance.org  ■ File Format: PDF files only  ■ File names must be maximum 60 characters long and must not contain any letter or special character other than from Latin alphabet/keyboard.  ■ All files must be free of viruses and not corrupted.  ■ Max. File Size per transmission: 10 MB  ■ It is recommended that the entire Quotation be consolidated into as few attachments as possible.  ■ The bidder should receive an email acknowledging email receipt.
Cost of preparation of quotation	ISA shall not be responsible for any costs associated with a Bidder's preparation and submission of a quotation, regardless of the outcome or the manner of conducting the selection process.
Supplier Code of Conduct, Fraud, Corruption,	All prospective suppliers must read the ISA Supplier Code of Conduct and acknowledge that it provides the minimum standards expected of suppliers to the ISA. The Code of Conduct, which includes principles on labour, human rights, environment and ethical conduct may be found at: <a href="https://isolaralliance.org/images/ISA%20Supplier%20Code%20of%20Conduct_14.4.2023.final%20version.pdf">https://isolaralliance.org/images/ISA%20Supplier%20Code%20of%20Conduct_14.4.2023.final%20version.pdf</a> Moreover, ISA strictly enforces a policy of zero tolerance on proscribed practices, including fraud, corruption, collusion, unethical or unprofessional practices, and obstruction of ISA vendors and requires all bidders/vendors to observe the highest standard of ethics during the procurement process and contract implementation.
Gifts and Hospitality	Bidders/vendors shall not offer gifts or hospitality of any kind to ISA staff members including recreational trips to sporting or cultural events, theme parks or offers of holidays, transportation, or invitations to extravagant lunches, dinners or similar. In pursuance of this policy, ISA: (a) Shall reject a bid if it determines that the selected bidder has engaged in any corrupt or fraudulent practices in competing for the contract in question; (b) Shall declare a vendor ineligible, either indefinitely or for a stated period, to be awarded a contract if at any time it determines that the

	vendor has engaged in any corrupt or fraudulent practices in competing for, or in executing a ISA contract.
Conflict of Interest	ISA requires every prospective Supplier to avoid and prevent conflicts of interest, by disclosing to ISA if you, or any of your affiliates or personnel, were involved in the preparation of the requirements, design, specifications, cost estimates, and other information used in this RFQ. Bidders shall strictly avoid conflicts with other assignments or their own interests, and act without consideration for future work. Bidders found to have an undisclosed conflict of interest shall be disqualified.
	The ISA shall have the discretion to disqualify or proceed with a bidder who has disclosed a probable conflict of interest subject to further evaluation and review of various factors such as access to sensitive information which may confer unfair advantage as against other bidders. The decision on a probable conflict of interest shall be made in the best interest of the work of the ISA.
	Bidders must disclose in their Bid their knowledge of the following: a) If the owners, part-owners, officers, directors, controlling shareholders, of the bidding entity or key personnel who are family members of ISA staff involved in the procurement functions and/or the Government of the country or any Implementing Partner receiving goods and/or services under this RFQ.
	The eligibility of Bidders that are wholly or partly owned by the Government shall be subject to ISA's further evaluation and review of various factors such as being registered, operated and managed as an independent business entity, the extent of Government ownership/share, receipt of subsidies, mandate and access to information in relation to this RFQ, among others. Conditions that may lead to undue advantage against other Bidders may result in the eventual rejection of the Bid.
General Conditions of Contract	Any Purchase Order or contract that will be issued as a result of this RFQ shall be subject to the General Conditions of Contract
	https://www.isolaralliance.org/images/ISA_GTB.pdf
Special Conditions of Contract	☐ Cancellation of PO/Contract if the delivery/completion is delayed by 10 days ☐ Others [pls. specify]
Pre-bid Conference	Not Applicable
Eligibility	A vendor who will be engaged by ISA may not be suspended, debarred, or otherwise identified as ineligible by any UN Organization or the World Bank Group or any other international Organization. Vendors are therefore required to disclose to ISA whether they are subject to any sanction or temporary suspension imposed by these organizations. Failure to do so may result in termination of any contract or PO subsequently issued to the vendor by ISA.
	It is the Bidder's responsibility to ensure that its employees, joint venture members, sub-contractors, service providers, suppliers and/or their employees meet the eligibility requirements as established by ISA.
	<ul> <li>Bidders must have the legal capacity to enter a binding contract with ISA and to deliver in the country, or through an authorized representative. Company registration certificate or any other document proving legal entity.</li> <li>The bidder must have the experience of supply of solar equipment's / hardware components. Submit copy of work order or completion certificate</li> <li>The bidder must have annual turnover of more than USD 100,000 - Please attach relevant documents.</li> </ul>

Currency of	Quotations shall be quoted in USD
Quotation	
Joint Venture,	If the Bidder is a group of legal entities that will form or have formed a Joint Venture (JV),
Consortium or	Consortium or Association for the Bid, they shall confirm in their Bid that : (i) they have designated
Association	one party to act as a lead entity, duly vested with authority to legally bind the members of the JV,
	Consortium or Association jointly and severally, which shall be evidenced by a duly notarized
	Agreement among the legal entities, and submitted with the Bid; and (ii) if they are awarded the
	contract, the contract shall be entered into, by and between ISA and the designated lead entity,
	who shall be acting for and on behalf of all the member entities comprising the joint venture,
	Consortium or Association.  Refer to Clauses 22 – 27 under Solicitation Process in the Procurement Manual (will be provided
	on request) for details on the applicable provisions on Joint Ventures, Consortium or Association.
Only one Bid	The Bidder (including the Lead Entity on behalf of the individual members of any Joint Venture,
Only one blu	Consortium or Association) shall submit only one Bid, either in its own name or, if a joint venture,
	Consortium or Association, as the lead entity of such Joint Venture, Consortium or Association.
	Bids submitted by two (2) or more Bidders shall all be rejected if they are found to have any of the
	following:
	a) they have at least one controlling partner, director or shareholder in common; or b) any one of
	them receive or have received any direct or indirect subsidy from the other/s; or
	b) they have the same legal representative for purposes of this RFQ; or
	c) they have a relationship with each other, directly or through common third parties, that puts
	them in a position to have access to information about, or influence on the Bid of, another Bidder
	regarding this RFQ process;
	d) they are subcontractors to each other's Bid, or a subcontractor to one Bid also submits another
	Bid under its name as lead Bidder; or
	e) some key personnel proposed to be in the team of one Bidder participates in more than one Bid received for this RFQ process. This condition relating to the personnel, does not apply to
	subcontractors being included in more than one Bid.
Duties and	The United Nations (privileges and immunities) Act, 1947 is applicable to ISA pursuant to a
taxes	notification by the host country. Therefore, ISA is exempt from all direct taxes, except charges for
	public utility services, and is exempt from customs restrictions, duties, and charges of a similar
	nature in respect of articles imported or exported for its official use in India. All quotations shall
	be submitted net of any direct taxes and any other taxes and duties, unless otherwise specified
	below:
	All prices must:
	☑ be inclusive of VAT and other applicable indirect taxes
	☐ be exclusive of VAT and other applicable indirect taxes  [according to project and applicable country agreement]
Language of	English
quotation	Including documentation including catalogues, instructions and operating manuals.
Documents to	Bidders shall include the following documents in their quotation:
be submitted	□ Annex 2: Quotation Submission Form duly completed and signed
	☑ Annex 3: Technical and Financial Offer duly completed and signed and in
	accordance with the Schedule of Requirements in Annex 1
	☐ Company Profile.
	☐ Registration certificate;
	☑ Company Profile.
	☑ Descriptive Literature: Bidders shall provide full technical details of products being offered,
	including technical sheets and pictures showing details and general views. Specific details of items
	offered should be clearly stated as standard catalogues may offer options;
	☑ Documents showing that the bidder has minimum of five (5) years of relevant experience – proof
	of purchase orders/ contract is to be submitted.
	☑ Documents showing that the bidder has an experience of design, supply, installation and
	commissioning of Grid connected/off grid Solar PV Power Plant and experience of rendering
	operation and maintenance services for Solar PV units.

	<del>-</del>
	☑ Statement of satisfactory Performance (Certificates) from the top two clients in terms of Contract value in similar field, plus client's contact details who may be contacted for further information on those contracts;
Quotation validity period	Quotations shall remain valid for 90 days from the deadline for the Submission of Quotation.
Price variation	No price variation due to escalation, inflation, fluctuation in exchange rates, or any other market factors shall be accepted at any time during the validity of the quotation after the quotation has been received.
Partial Quotes	<ul> <li>☑ Not permitted</li> <li>☐ Permitted Insert conditions for partial quotes and ensure that the requirements are properly listed in lots to allow partial quotes</li> </ul>
Alternative Quotes	□ Not permitted     □
Payment Terms	☑ Within 30 days upon ISA's acceptance and receipt of invoice.
Conditions for Release of	☑ Written Acceptance of Goods & Services, based on full compliance with RFQ requirements.
Payment	<ul> <li>✓ 100% of goods charges after successful delivery and acceptance of goods.</li> <li>✓ 100% of Installation &amp; Commissioning charges after successful installation and commissioning</li> <li>✓ 100% of training charges after completion of Training on Operation and Maintenance.</li> <li>✓ 100% of Comprehensive maintenance charges after successful 1 year of installation and commissioning</li> </ul>
Contact Person for	E-mail address: anupol@isolaralliance.org  Attention: Quotations shall not be submitted to this address but to the address for quotation
correspondenc	submission above. Otherwise, offer shall be disqualified.
e, notifications and clarifications	Any delay in ISA's response shall be not used as a reason for extending the deadline for submission, unless ISA determines that such an extension is necessary and communicates a new deadline to the Proposers.
Clarifications	Requests for clarification from bidders will not be accepted any later than 2 days before the submission deadline. Responses to request for clarification will be communicated thru email.
Evaluation method	⊠The Contract or Purchase Order will be awarded to the lowest price substantially compliant offer
Evaluation criteria	<ul> <li>         ⊠ Full compliance with all requirements as specified in Annex 1     </li> <li>         ⊠ Full acceptance of the General Conditions of Contract     </li> <li>         ⊠ Comprehensiveness of after-sales services     </li> <li>         □ Earliest Delivery /shortest lead time     </li> <li>         □ Others Click or tap here to enter text.     </li> </ul>
Right not to accept any quotation	ISA is not bound to accept any quotation, nor award a contract or Purchase Order
Right to vary requirement at time of award	At the time of award of Contract or Purchase Order, ISA reserves the right to vary (increase or decrease) the quantity of services and/or goods, by up to a maximum twenty-five per cent (25%) of the total offer, without any change in the unit price or other terms and conditions.
Type of Contract to be awarded	☐ Purchase Order ☐ Contract for Works ☐ Other Type/s of Contract [pls. specify]

Expected date for contract award.	30 June 2023
Publication of Contract Award	ISA will publish the contract awards valued at USD 100,000 and more on the ISA website.
Policies and procedures	This RFQ is conducted in accordance with ISA Financial Regulation and Procedures and ISA procurement manual
Other Provisions	The ISA is striving to achieve gender parity in all its activities. In this regard, female-owned organizations and/or teams with significant gender diversity are strongly encouraged to submit a proposal.
	The ISA recognizes the importance of valuing diversity and promoting inclusion in all our work programs and partnerships. The ISA strives to engage with organizations and/or teams that reflect its geographical representation and diversity.

## **ANNEX 1: SCHEDULE OF REQUIREMENTS**

Recognizing the urgent need to support the developing country (ISA members) with high potential for solar technology deployment, the ISA Assembly agreed to establish an international network of STAR C (Solar technology Application Resource Centre). The overarching objective of the STAR C initiative is to provide solar technology and application resourcing services to Member Countries so that these countries can achieve the ISA's vision of scaled up and accelerated large scale deployment of solar energy to meet the respective countries' priority energy access, energy transformation and energy security needs.

ISA aims to a have number of STAR centres across the globe acting as a shared facility that provides capacity for deployment of solar energy applications and research, business modelling, incubation, training, standardization and testing engaging faculty members from different disciplines/institutes of excellence and provide/use shared facilities, labs, testing centres etc.

In order to equip these STAR Centres, ISA aims to procure equipment and instruments that help the centres to offer hands on training; act as a testing facility and setup a knowledge management centre.

Such centres are being created by ISA in Somalia. The host institution for the STAR Centre in **Somalia is the Somalia National University.** 

This RFQ is for Supply, Installation, Testing & Commissioning (SITC) of equipment and instruments for setting up the STAR Centre in Somalia including one-year Comprehensive Maintenance Contract (CMC).

A needs assessment and situation analysis were undertaken in Somalia, to identify the high growth sectors within solar energy technology, and the attendant training needs. SHS, PV Parks, Solar rooftop and Solar Pumps are the three high growth sectors in Somalia. These sectors will drive solar training needs in the medium to long term and require trained technicians and engineers to size, install, operate and maintain solar systems for socio-economic development, especially in rural and peri-urban areas. The current solar training and testing facilities as well as the solar curriculum was evaluated for gaps through secondary research and primary stakeholder interviews with the private sector companies, industry bodies, government, and academia.

The major findings were the need for understanding of the various solar components, design, sizing, installation, operations, and maintenance. According to the evaluation of the needs and gaps, a list of solar equipment has been suggested for the STAR C to prioritize in its implementation. A detailed list of the technical specifications is provided:

**Recommended Technical Specifications for Goods** 

Item	Equipment	Specification EN	Quantity	Unit
Α	Tools and instruments			
A1	Personal Protective Equipment	Specification	Quantity	Unit
1	Reflective vests	Reflective vests	20	pieces
2	Helmets	Helmets	20	pieces
3	Work gloves	Work gloves	20	pairs
A2	Instruments	Specification	Quantity	Unit
4	Digital multimeter (medium quality)	TRMS values, capable of measuring AC (750 V) & DC (1000 V) voltages, DC current 10 A, continuity/resistance, fused for current measurements, overvoltage CAT III 1,000 V and CAT IV 600 V.  Lower-cost instruments are suitable for work board exercises	6	pcs
5	Spare fuses for above multimeter (medium quality)	30 of each type of fuse in multimeter	30	pcs
6	Digital multimeter (professional standard)	TRMS values, Capable of measuring 1000 V AC/DC voltages, DC current 10 A, continuity/resistance, fused for current measurements, overvoltage CAT III 1,000 V and CAT IV 600 V, temperature probe, test leads and accessories  This needs to be a 'professional standard' instrument such as the the Fluke 179 or similar	2	pcs
7	Spare fuses for above multimeter (professional standard)	5 of each type of fuse in multimeter	5	pcs
8	Clamp meter (medium quality)	Capable of measuring AC & DC (600 V) voltages, DC and AC current ranges 40 A / 400 A, continuity/resistance, overvoltage CAT III 600 V. Lower-cost instruments are suitable for work board exercises	6	pcs

9	Clamp meter (professional standard)	TRMS values, capable of measuring AC & DC (600 V) voltages, DC and AC current ranges 40 A / 400 A, continuity/resistance, overvoltage CAT III 600 V and CAT IV 300 V. This needs to be a 'professional standard' instrument such as the the Fluke 325 or similar	1	pcs
10	Insulation resistance tester	Capable of measuring insulation resistance at 250 V, 500 V and 1000 V, isolations-resistance measurement to 20 G $\Omega$ , resistance measurement 0,01 $\Omega$ - 20 k $\Omega$ , AC voltage measurement 0 - 500 V AC, overvoltage CAT IV 600 V	1	pcs
11	Plug-in wattmeter	To fit AC sockets being used in country (Type C, D or G sockets, the most common one to be selected); capable of measuring appliance power consumption (W), energy (kWh) and cost of electricity consumed	3	pcs
12	Hand-held solar irradiance meter	Capable of measuring solar irradiation, hand-held, 0 - 2000 W/m2 range, resolution 1 W/m², digital display	1	pcs
13	Infrared thermometer	Hand held laser Infrared thermometer, -20 to 100 ° C minimum range, digital display	1	pcs
14	Solar Pathfinder	The Solar Pathfinder is the instrument specified.It is relatively low-cost, does not require batteries and is ideal for didactic purposes.To be supplied with tripod.	2	pcs
15	Sun path diagrams for the Solar Pathfinder (only if Solar Pathfinder can be procured)	For correct latitudes: Available from manufacturer/supplier of Solar Pathfinder	15	pcs
16	Compass	Basic, low cost, pocket size compass, of type used by walkers	4	pcs
А3	Tools	Specification	Quantity	Unit

17	Crimp/termination tools for PV interconnectors	For MC4 PV module connectors, 4-6mm <sup>2</sup> wires (minimum range)	2	pcs
18	Crimping tool kit & crimps	Crimping tool kit & supply of 800 min. crimps/lugs. For insulated cable lugs from 0.5 to 6 mm² (red-blue-yellow) and non-insulated cable lugs from 1.5 to 10 mm², VDE certified	3	pcs
19	Electrician's tools kit	Set of electricians' insulated hand tools, screwdrivers, pliers, cable cutter, cable stripper, 1000 V insulation, standard IEC EN 60900	20	pcs
20	Adjustable spanners	Maximum opening: 30 mm	3	pcs
21	Spanner set	For nuts and bolts widths 6 - 22 mm (recommended range)	2	pcs
22	Screwdriver set for precision mechanics	For single slot and Philipps screws: 6 different standard sizes	2	pcs
23	Basic vehicle mechanics tools set	Basic set, socket set, suitable for work on cars and motor cycles, metric	2	pcs
24	Long tape measures	Also called builder/surveyor's tapes, 20m or more, fibreglass tape (not steel), metric	3	pcs
25	Hydrometer	For measuring battery electrolyte specific gravity	3	pcs

26	Allen key set	Key sizes: 1.5 - 10 mm approx.	2	pcs
27	Clipboards	Suitable for outdoor use, A4, perspex	15	pcs
A4	Extras and spares	Specification	Quantity	Unit
28	Safety harness kit for working at height / on roofs	Complete kit. including harness, fall arrest lanyard, D rings, and packing case/rucksack	2	pcs
29	Replacement batteries for multi- und clamp meters	spare part for multimeters, check requirements of procured meters and provide multiple spare batteries of all required types	20	
30	multimeter special cables (thermocouples, croco clamps, etc.)	only if not supplied with original equipment	10	
31	Soldering iron/station	60W, 230 Volts	2	pcs
32	Soldering tips	according to soldering station	5	pcs
33	Solder	100g roll, lead-free	2	pcs
34	Multiple socket strip with personal protection	5+ sockets	2	pcs
35	Hot air gun		2	pcs
36	Schottky Diode 15 A 45 V	THT axial bypass diode, 15A, 45V	25	pcs
37	Soldering station	Adjustable temperature range (100°C-450°C), 70W, 5 different solder tips, tip stand and sponge	2	pcs
38	Multifunction Tool	Battery powered, fully variable speed 5.000 35.000 1/min, at least with 30 accessories, 12VDC, carry case	2	pcs
39	Bench power supply	1-channel, adjustable voltage 0VDC-40VDC, display, adjustable current 0A-10A, 150W minimum	2	pcs
40	Anti-static pad for work space with earth wall plug	heat-resistant, DIN EN 61340-5-1 , 0.5m x 0.3m minimum	2	pcs
41	Anti-static wrist band with earthing connection	anti-static wrist band with cable and compatible with pad	3	pcs

В	PV EXERCISE BOARDS			
	PV modules	Specification	Quantity	Unit
1	PV module	PV module, <b>polycrystalline</b> , 36 cells, 120 Wp approx., 20 Voc approx., 36 cells, aluminium frame, junction box not pre-cabled (openable, not sealed), product certification IEC 61215	3	pcs
2	PV module	PV module, <b>monocrystalline</b> , 36 cells, 120 Wp approx., 20 Voc approx., 36 cells, aluminium frame, junction box not precabled (openable, not sealed), product certification IEC 61215	3	pcs
3	PV module	Mono or polycrystalline, 150 Wp approx., 40 Voc approx., 72 cells, aluminium frame, junction box not pre-cabled (openable, not sealed), product certification IEC 61215	3	pcs
4	PV module	20 -50 Wp (small), monocrystalline and polycrystalline, 20 Voc approx., 36 cells, aluminium frame, junction box not precabled (openable, not sealed), product certification IEC 61215, a selection of different types	α	pcs
	PV cable connectors	Specification	Quantity	Unit
5	PV module inter- connection connectors (male)	MC4 male connectors for 4 mm <sup>2</sup> solar cable. and suitable for above crimp/termination tool, IP65, 30 A, 1000 DC	100	pcs
6	PV module inter- connection connectors (female)	MC4 female connectors for 4 mm <sup>2</sup> solar cable. and suitable for above crimp/termination tool, IP65, 30 A, 1000 DC	100	pcs
7	PV module inter-	MC-4 compatible PV connectors, male,	100	pcs
	connection connectors (female)	which do not require specialised tools, for 4 mm <sup>2</sup> solar cable, IP65, 30 A, 1000 DC	100	ρcs
8		which do not require specialised tools, for 4	100	pcs
8	(female)  PV module inter- connection connectors	which do not require specialised tools, for 4 mm² solar cable, IP65, 30 A, 1000 DC  MC-4 compatible PV connectors, female, which do not require specialised tools, for 4		
	(female)  PV module inter- connection connectors (male)	which do not require specialised tools, for 4 mm² solar cable, IP65, 30 A, 1000 DC  MC-4 compatible PV connectors, female, which do not require specialised tools, for 4 mm² solar cable, IP65, 30 A, 1000 DC  MC4 compatible Y-connector for parallel	100	pcs

11	Solar charge controller	overload protection, low voltage disconnect, reverse polarity protection, temperature compensation, open circuit protection when not connected to battery, IP 20 min., 2-year manufacturer's warranty  20A solar module current / 20A load current	3	pcs
	(standard, without MPPT)	minimum, other specs as above		
12	Solar charge controller (with MPPT)	25 A min. approx. (in/out), 12/24 V, with MPPT range 17 V 100+ V (34 V 100+ V approx.), LC display, cable input/output terminals for 10 mm² cable min., for leadacid batteries, overload protection, low voltage disconnect (deep discharge protection), regular equalisation charge, overcharge protection, reverse polarity protection, temperature compensation, open circuit protection when not connected to battery, IP 20 min.	2	pcs
13	Inverter (battery inverter)	12 V DC input, from 220 - 240 V 50 Hz power output, 200 - 500 W (200 - 500 VA continuous power), pure sine wave, IP 20 min, overload and short circuit protection, reverse polarity protection as internal fuse, deep discharge battery protection, to be sourced from a supplier of equipment for PV systems and recommended by that PV supplier for use in off-grid PV systems (not a cheap inverter of the type used in motor vehicles), not to contain integrated solar charge controller  If possible provide inverters from 2 different manufacturers	6	pcs
14	DC lamps, 12 V, florescent	12 V, florescent lamps with replaceable bulb/tube 3 x 7 W 3 x 9 W 3 x 11 W	12	pcs
15	DC lamps, 12 V, LED	12 V DC, LED, 2 W, E27, 200 lumens min., warm white various wattage, e.g. 3 x 5 W 3 x 10 W 3 x 15 W	12	pcs
16	DC lamps, 12 V halogen	12V, halogen, with reflectors, selection between 10W and 40W	12	pcs
17	Lamp holders	E 27 lamp holder, plastic, heavy duty, for surface mounting on work board	14	pcs

18	DC fans	12 V DC desk fan. 10 W min., 20 W max.	3	pcs
19	DC/DC converter	DC/DC converter, 12 V to 24 V, 1,5 A minimum output	6	pcs
20	DC sockets	Socket outlet for 12/24 V DC, for surface mounting on work board	12	pcs
21	DC plugs	DC plugs to fit above DC sockets	12	pcs
22	Junction boxes	100 x 100 x 40 mm (LxWxH) approx., surface mounting (for work board)	30	pcs
23	DC miniature circuit breakers	DC miniature circuit breaker, 1-pole, 80VDC, 6A tripping current, 1 pole, suitable for DIN rail mounting	6	pcs
24	DC miniature circuit breakers	DC miniature circuit breaker, 1-pole, 80VDC, 10A or 16A tripping current, 1 pole, suitable for DIN rail mounting	12	pcs
25	DC miniature circuit breakers	DC miniature circuit breaker, 1-pole, 80VDC, 40A or 50A tripping current, 1 pole, suitable for DIN rail mounting	8	pcs
	AC exercise boards	Specification	Quantity	Unit
26	Consumer unit / fuse board	To fit DP main switch and 2 - 3 MCBs and E terminal, for 220 - 240 V 50/60 Hz power supply, IP65	3	pcs
27	Miniature circuit breaker (MCB) AC	Single-pole, 6A, Type B, 220 - 240 V 50/60 Hz, to fit above consumer unit / fuse board	3	pcs
28	Miniature circuit breaker (MCB) AC	Single-pole, 16A, Type B, 220 - 240 V 50/60 Hz, to fit above consumer unit / fuse board	3	pcs
29	Residual current device (RCD)	Type A 25A 30mA RCD, 220 - 240 V 50/60 Hz, to fit above consumer unit / fuse board	3	pcs
30	Socket outlet	Type C 230 V, 2 pole excl. Grounding surface mounted (incl box for surface mounting on board), indoor use, IP22 or IP2X min.	8	pcs
31	Socket outlet	Type D 230 V, 3 pole incl grounding surface mounted (incl box for surface mounting on board), indoor use, IP22 or IP2X min	8	pcs
32	Socket outlet	Type G 230 V, 3 pole incl grounding surface mounted (incl box for surface mounting on board), indoor use, IP22 or IP2X min.	8	pcs
33	Plug	Type C, to fit above sockets	4	pcs
34	Plug	Type D, to fit above sockets	4	pcs
35	Plug	Type G, to fit above sockets	4	pcs

36	Connector blocks / terminal strips	Screw terminal strip, 3A, 400VAC, for 2.5 mm2 cable (10-12 connector blocks per strip, 240 blocks in total )	25	strips
37	Connector blocks / terminal strips	Screw terminal strip, 6A, 400VAC, for 4 mm2 cable (10-12 connector blocks per strip, 240 blocks in total )	25	strips
38	Connector blocks / terminal strips	Screw terminal strip, 16A, 400VAC, for 6 mm2 cable (10-12 connector blocks per strip, 240 blocks in total )	25	strips
39	Earth blocks	4-Way Earth Block Nickel-plated, Suitable for 16-25mm <sup>2</sup> Cables, Brass Construction	6	pcs
	Cables, etc.	Specification	Quantity	Unit
40	Flex	1.5 mm2 flexible cable for connecting appliances to plugs, 3-core incl. PE), very flexible, copper. PVC sheathed, H05-VVF, 50 m roll	2	pcs
41	Cable	1.5mm2, 2-core (no PE), <u>multi-stranded</u> , very flexible, copper, PVC sheathed, H05-VVF, 50 m roll	2	pcs
42	Cable	2.5mm2, 2-core (no PE), <u>multi-stranded</u> , very flexible, copper, PVC sheathed, H05-VVF, 100 m roll	2	pcs
43	Cable	2.5 mm2 flexible cable for connecting appliances to plugs, 3-core incl. PE), very flexible, copper. PVC sheathed, H05-VVF, 50 m roll	2	pcs
44	PV cable / 'solar cable'	4 mm2, double insulated, single-core, UV protected, cable specified for the interconnection of PV modules, <u>fine</u> multistranded, copper, temperature rating -40°C - 90°C, 1000 DC, Class II (double insulated), halogen free, flame resistant, 100 m roll	4	pcs
45	Cable	6 mm2 single-core, <u>fine multi-stranded</u> , PVC, red, very flexible, copper, unsheathed, H07V-K 100 m red roll	2	pcs
46	Cable	6 mm2 single-core, <u>fine multi-stranded</u> , PVC, red, very flexible, copper, unsheathed, H07V-K 100 m black roll	2	pcs

47	Cable	6 mm2 single-core, <u>fine multi-stranded</u> , PVC, red, very flexible, copper, unsheathed, H07V-K 100 m yellow-green roll	2	pcs
48	Cable	10 mm2 single-core, <u>fine multi-stranded</u> , PVC, red, very flexible, copper, unsheathed, H07V-K 100 m red roll	2	pcs
49	Cable	10 mm2 single-core, fine multi-stranded, PVC, red, very flexible, copper, unsheathed, H07V-K 100 m black roll	2	pcs
50	Cable	10 mm2 single-core, <u>fine multi-stranded</u> , PVC, red, very flexible, copper, unsheathed, H07V-K 100 m yellow-green roll	2	pcs
51	Electrical insulation tape	25 m length rolls, 20 mm width, approx., max heat resistant temperature 90 °C 5 x red 10 x black 5 x blue 5 x yellow/green	25	rolls
	Batteries & accessories	Specification	Quantity	Unit
52	Battery	12 V lead gel, 60 - 90Ah, sealed, maintenance-free, 'solar batteries'	8	pcs
53	Battery terminals (pairs)	To fit above battery	10	pcs
54	Lead-acid batteries	12 V lead-acid, 60 - 90Ah, flooded, 'solar batteries', dry, to be filled with supplied acid at site	5	pcs
55				
F.C.	Battery terminals (pairs)	To fit above battery	6	pcs
56	Battery terminals (pairs)  Battery charger	To fit above battery  Suitable for charging sealed 12 V 100 Ah lead-acid battery, from 220 - 240 V 50/60 Hz power supply, charging rate 0.8 A / 3.6 A, robust quality, IP65	6 2	pcs
56		Suitable for charging sealed 12 V 100 Ah lead-acid battery, from 220 - 240 V 50/60 Hz power supply, charging rate 0.8 A / 3.6 A,		•
	Battery charger	Suitable for charging sealed 12 V 100 Ah lead-acid battery, from 220 - 240 V 50/60 Hz power supply, charging rate 0.8 A / 3.6 A, robust quality, IP65  For safely pouring distilled water into	2	pcs

С	HYBRID SYSTEM			
		300+ W each, mono- or polycrystalline, IEC	16	pieces
1	PV modules	certified	10	pieces
		-Should have the capacity to charge the		
		battery bank from PV solar and Electricity		
		with option of priority setting.		
		- Three-phase connection (single-phase		
		optional if three-phase system not common)		
		- 5000 W AC output, capable to provide		
	Hybrid inverter	backup power in case of grid-failure		
2		- Min. 5000 W PV power to be connected		
		Cell chemistry: LiFePo4		
		- Min. 4000 Wh usable storage capacity at		
		100% DOD)		
		- Min. 4000 cycles	4	
		- system voltage and integrated BMS	1	piece
		compatible with the installed battery (or		
		hybrid) inverter (certified by manufacturer		
3	Battery system	of inverter)		
		If not included as a functionality of the		
		battery inverter (or hybrid inverter), provide		
		a separate monitoring system that monitors		
		the main system parameters and sends them		
4	Monitoring	to the manufacturer's data portal.		
	-	set to include all wires, connectors,		
		distribution boxes, switchgear, fuses,	4	
		installation material to integrate a fully	1	set
5	BOS-set	operational system		
		4mm <sup>2</sup> DC solar cable: double-insulated, UV-	200	
6	Consumables	resistant, single core, black	200	m
		DC-connectors: MC4, Sunclix or similar for	F0	
7	Consumables	4mm² cable, male	50	pieces
		DC-connectors: MC4, Sunclix or similar for	50	
8	Consumables	4mm² cable, female	50	pieces
9	Consumables	Cable ties, 20 cm, UV-resistant	400	pieces
		Ground-mounted mounting system for 20		•
		solar modules of the model offered in this	1	set
10	Mounting	bid (item 1)		
	Ŭ T	Concrete ballast for mounting system	4.0	
11	Mounting	foundation	10	pieces
	Ĭ	Concept, engineering, procurement,		
		shipping, installation, and commissioning of		
		hybrid system	_	lump
		- to include a complete set of system	1	sum
		documentation (manuals, datasheets, SLD,		
12	EPC-service	wiring diagrams, etc.)		
D	SOLAR HOME SYSTEM			
	Solar Home System	PV = min. 300Wp		
	Installation (made up of	Inverter = min. 500W nom.		
	the following components)	Charge controller if Inverter does not		
		include charge controller		
	J		l .	1

		Battery display required showing SoC in %, Ampere in/out Battery Voltage, etc. Battery = min. 2.4kWh @c10 set, complete mounting board with pre- installed material as noted below for complete turn-key installation and additional consumables (e.g., wires, fuses, battery fuses, combiner and distribution boxes, load centre, earthing system, surge protection devices, etc.) lump sum, turn-key installation at site by a qualified technician Documentation for all technical products shall be available		
1	Solar Charge Controller MPPT	Nominal Power range 400 W Nominal Voltage (PV Input) max 42 VDC (if designed as 24 VDC system a DC/DC converter will be needed to ensure that standard 12 VDC appliances/loads can be used. Converter can be included into load distribution box if cooling is sufficient under load.) Nominal PV Input Current range 520 A Nominal Voltage (Load Output) 12 VDC Nominal Current (Load Output) min 25 A Nominal Battery Voltage range 1224 VDC (autodetect feature mandatory) Operating Temperature range 050 °C MPPT Technology 3-Way Battery Charging Profile or better (battery voltage setpoints according to used battery chemistry in 2.0) IP Class Overcharging Protection, adapted to batteries offered Charging Profile, adapted to batteries offered Overload Protection (the solar charge controller must be able to handle the situation when a battery is not being connected while PV is already providing power to it) Over-temperature Protection Short Circuit Protection Battery Temperature Compensation (if not available a Battery Temperature Sensor is mandatory) Reverse Polarity Protection on PV and battery terminals (A reverse polarity event shall be resettable without replacing blown	1	pcs

2	VRLA AGM Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including interconnection, cable, screws, isolator, and cable to Battery Fuse and from Fuse to Inverter> Charge controller	fuses. MCBs are preferred but Polyfuses or Crowbar circuit might be an option. If not provided by the charge controller it has to be provided by an external circuit or device. Internal fuses can't be changed locally and will result in unusable equipment) Status Display, Soc in %  Nominal Voltage 12 VDC Nominal Capacity (C10) min 100 Ah Charge Cycles at 50% DoD min 1400 Maintenance Free, AGM (has to be a solar battery suitable for daily dis/charge cycles)DC Battery Fuse	2	pcs
3	PV Modules Total min 300Wp, Voltage suitable for Charge Controller, Inverter	PV saline protection (IEC 61701) if location is close to the sea  Nominal Power per PV Module min 150 W (when using multiple PV Modules they have to be the same manufacturer and model) Open Circuit Voltage (STC) max 42 VDC Bypass diodes min 3 Reverse Current min 15 A Voltage Capability min 1000 VDC IP Class Junction Box min IP65 Temperature Range -4085°C Cell Efficiency min 18% Power Tolerance max 5% MC4 Compatible Connectors Monocrystalline or Polycrystalline Technology	2	pcs
4	Roof Mounting Substructure, Aluminium for Metal sheet Roof with wooden Screws for wooden substructure on a training rood		2	pcs
5	Remote Monitoring Device	compatible with solar charge controller unit or Inverter can be wireless (Bluetooth, Wi-Fi) or wired. When wired it has to be USB compliant. If this can be only achieved with a converter it needs to be provided and documented. Compatible with PC (MS Windows) or Android Smartphone	1	pcs
6	DC Load Distribution Box	Nominal voltage 12 VDC DC Connectors female 5.5/2.1 mm, 2 pcs min 3 A DC Connectors female 5.5/2.5 mm, 2 pcs min 3 A	1	pcs

		DC Connectors female 4mm safety terminals, 2 pcs min 16 A compatible with 4mm safety cables connector DC Connectors female USB type A, 1 pcs min 0.5 A can also be provided by solar charge controller if available DC Connectors female USB type A, 1 pcs min 1.5 A can also be provided by solar charge controller if available		
7	Inverter	"Nominal Power at 20°, Suitable for humidity > 80 % " max 500 W Nominal Voltage Input 12 VDC Nominal Voltage Output range 220240 VAC one IEC Type F outlet is sufficient but adapter for Type M must be provided Nominal Frequency 50 Hz Nominal Continuous Output Current min 1.4 A Nominal Peak Output Current min 3 A True Sine Wave Dedicated Power Switch Overload Protection Over-temperature Protection Short Circuit Protection	1	pcs
8	Mounting Board	all components besides PV modules and batteries shall be installed on a mounting board Dimensions: Width max 12 m, depth max 0.5 m including installed components on mounting structure, Height max 11.5 m Material, Coating and Grounding as defined by manufacturer and local rules	1	pcs
	Solar Home System Kit	by managed of and local rates		
9	Solar Home System Kit or Bundle	Verasol Certification, Lithium Iron Phosphate Battery, GSM (mobile network) remote monitoring, PAYGO integration, MPPT controller, PV input power up to 100W,	1	pcs
10	SHS Solarworx lamps 1W		5	pcs
11	SHS Solarworx 32 inch TV		1	pcs
12	SHS Solarworx fridge		1	pcs

13	SHS Solarworx Victron PayG Dongle or switch		1	pcs
_	COLAD STREET LICHT			
E	SOLAR STREET LIGHT Solar street light outdoor			
1	Solar Street Light Kit	Park lamp for public areas and paths, 12W high efficiency LEDs, 1620 lumens, incl. lamp bracket, module mounting structure, top of pole mount battery box, solar charge controller with time program function, 80Wp module, 60Ah sealed battery	1	pcs
2	Lamp post for Street Light Kit	lamp post 5 metres heigh with accessories for ground assembly, corrosion safe (anodized)	1	pcs
3	Scaffold complete assembly	TÜV certified; 5,30 m working height, 200 kg/m² load according to DIN EN 1004-1; movable with castors	1	pcs
4	Scaffolding Elevator Console with Pulley	compatible with scaffolding system, load capacity: minimum 200 kg; rope and attachment to pull up batteries and PV modules to train part exchange	1	pcs
5	Ladder	6 m working height with stair function, aluminium, must withstand up to 150kg	1	pcs
	Solar street light indoor			
1	100Wp Solar Street Lighting System, 20 W LED light (made up of the following components)	set, complete mounting board with pre- installed material as noted below for complete turn-key installation and additional consumables (e.g., wires, fuses, battery fuses, combiner and distribution boxes, load centre, earthing system, surge protection devices, etc.) lump sum, turn-key installation at site by a qualified technician Documentation for all technical products shall be available		
2	Solar Charge Controller MPPT	Nominal Power range 200 W Nominal Voltage (PV Input) max 42 VDC (if designed as 24 VDC system a DC/DC converter will be needed to ensure that standard 12 VDC appliances/loads can be used. Converter can be included into load distribution box if cooling is sufficient under load.) Nominal PV Input Current range 515 A	1	pcs

3	VRLA Gel Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including interconnection, cable, screws, isolator, and cable to Battery Fuse and from Fuse to Inverter> Charge controller	Nominal Voltage (Load Output) 12 VDC Nominal Current (Load Output) min 10 A Nominal Battery Voltage range 1224 VDC (autodetect feature mandatory) Operating Temperature range 050 °C MPPT Technology 3-Way Battery Charging Profile or better (battery voltage setpoints according to used battery chemistry in 2.0) IP Class Overcharging Protection, adapted to batteries offered Charging Profile, adapted to batteries offered Overload Protection (the solar charge controller must be able to handle the situation when a battery is not being connected while PV is already providing power to it) Over-temperature Protection Over-voltage Protection Short Circuit Protection Battery Temperature Compensation (if not available a Battery Temperature Sensor is mandatory) Reverse Polarity Protection on PV and battery terminals (A reverse polarity event shall be resettable without replacing blown fuses. MCBs are preferred but Polyfuses or Crowbar circuit might be an option. If not provided by the charge controller it has to be provided by an external circuit or device. Internal fuses can't be changed locally and will result in unusable equipment) Status Display, Soc in % Nominal Voltage 12 VDC Nominal Capacity (C10) min 50 Ah Charge Cycles at 50% DoD min 1400 Maintenance Free (has to be a solar battery suitable for daily dis/charge cycles)DC Battery Fuse	2	pcs
4	Charge controller  DC bench power supply (to simulate PV modules)	at least 2 channels; adjustable 0 - 30 VDC; 0 - 3A; 195W;	1	pcs
	·	Resolution: Voltage: ≤0.01% + 2mV ; Current: ≤0.01% + 250uA		
5	Remote Monitoring Device	compatible with solar charge controller unit or Inverter can be wireless (Bluetooth, Wi-Fi) or wired. When wired it has to be USB compliant. If	1	pcs

		this can be only achieved with a converter it needs to be provided and documented. Compatible with PC (MS Windows) or Android Smartphone		
6	DC Load Distribution Box	Nominal voltage 12 VDC DC Connectors female 5.5/2.1 mm, 2 pcs min 3 A DC Connectors female 5.5/2.5 mm, 2 pcs min 3 A DC Connectors female 4mm safety terminals, 2 pcs min 16 A compatible with 4mm safety cables connector DC Connectors female USB type A, 1 pcs min 0.5 A can also be provided by solar charge controller if available DC Connectors female USB type A, 1 pcs min 1.5 A can also be provided by solar charge controller if available	1	pcs
7	LED lamp	2x60cm tube, 20-26VDC, 920mA, 22W, 4000K, 2200lm, G13, IP22	1	pcs
8	LED lamp	Nominal Power, range 20 W Nominal Voltage Input 12 VDC Luminous Flux min 5000 Im heat dissipation of the lamp shall not affect other components on the mounting board. Colour Temperature min 5500 K Radiation Angle min 120° lamp screen shall be parallel to the floor (90° angle between mounting board in upright position and lamp screen) so that blinding of personnel is prevented Working Life min 25,000 h On/Off Cycles min 100,000 Temperature Range, range -2065°C IP Class min IP65 Material Aluminium and Glass Lamp Post or mounting bracket for board mounting must be included (negotiable if lamp itself already covers this by design) Length of LED Lamp and Lamp Post max 1 m (may exceed mounting board dimensions but shall be removable for transport)	1	pcs
9	Twilight Switch /w Relay (not mandatory if already included in LED Lamp)	Nominal Voltage 12 VDC  Nominal Switching Power min 30 W  Switching Capability Power according to selected LED lamp in 6.0 (must switch LED lamp safely with enough headroom power)	1	pcs

10	Movement Sensor (not mandatory if already included in LED Lamp)	detection angle: 180°, programmable twilight and switching time, IP44, 12-24 V	1	pcs
11	Mounting Board	Dimensions: Width max 12 m, depth max 0.5 m including installed components on mounting structure, Height max 11.5 m Material, Coating and Grounding as defined by manufacturer and local rules	1	pcs
12	Mobile work bench	including RCD with 6 AC outlets, electrically safe and acid resistive coating, dimensions: 1250 x 1970 x 700 mm	1	pcs
F	SOLAR WATER PUMPING SYSTEM OUTDOOR and INDOOR			
	Solar water pumping outdoor			
1	Reservoir	water will be pumped from one reservoir to the other and vice versa using two pumps Volume min 1000 litres (1m³) Material Non-Corrosive Big Top Opening Opening Valve at the Bottom	2	pcs
2	Flange for reservoir connection with outlet tap	output flange in metal according to reservoir outlet, including shutter valve	2	pcs
3	Water pipe DN 50	water pipe compatible with flange above to connect to the surface pump, can be sewage type, installation needs to cover all eventual misalignments or deviations from horizontal or vertical positioning of pumps and reservoirs	2	pcs

4	Surface pump complete kit	Complete kit containing: - surface pump - surface pump controller - surface pump switch box - surface pump controller for AC grid connection as backup - 2x 330 Wp PV Modules, - MNPV3 combiner box - MC4 extension cable - top of pole solar panel mount - 40 steel pipe - grounding lugs - submersible pump cable - submersible pump water lifting pipe - water level switch - lightning arrestors	1	pcs
5	Submersible pump complete kit	Complete kit containing:- submersible pump- submersible pump controller- submersible pump1 controller for AC grid connection as backup- 2x 330 Wp PV Modules,- MNPV3 combiner box- MC4 extension cable- top of pole solar panel mount- 40 steel pipe- grounding lugs- submersible pump cable- submersible pump water lifting pipe- water level switch-lightning arrestors	1	pcs
6	Cast resin sleeve for submersible pump electric connection	Pass 3 x 1,5 to 5 x 6mm <sup>2</sup> , lateral 3 x 1,5 to 5 x 4mm <sup>2</sup> , hardener 0,225kg, incl. sleeve, polyurethane cast-resin, hardener, gloves, two foam seals and abrasive paper	20	pcs

7	Submersible cable to train cast resin application	Submersible cable	50	metres
8	Water pressure gauge	PRESSURE GAUGE WITH TEE 0-60PSIG, EA	2	pcs
9	Closing valve	Ball valve with spring return DN40 - 1 1/2" inch GK13, brass	4	pcs
10	Water flow meter	Range: 240 l/min, Pressure: min. 12 bar; temperature control; compatible with water pipe diameters (adapters must be supplied if device differs from piping), display with values in metric, IP65, supply voltage according to pump electrical specifications (power supply must be supplied if device cannot be powered from the pump controller)	2	pcs
11	PV Modules Total min 300Wp, Voltage suitable for Charge Controller, Inverter AS REFERENCE FOR THE PV	PV saline protection (IEC 61701) if location is close to the sea Nominal Power per PV Module min 300 W (when using multiple PV Modules they have to be the same manufacturer and model) Open Circuit Voltage (STC) max 42 VDC	4	pcs

	MODULES INCLUDED IN PUMP KITS ABOVE!	Bypass diodes min 3 Reverse Current min 15 A Voltage Capability min 1000 VDC IP Class Junction Box min IP65 Temperature Range -4085°C Cell Efficiency min 18% Power Tolerance max 5% MC4 Compatible Connectors Monocrystalline or Polycrystalline Technology		
12	Roof Mounting Substructure, Aluminium for Metal sheet Roof with wooden Screws for wooden substructure on a training rood		12	pcs
	Solar water pumping indoor			
13	500700 W Solar Water Pumping System (made up of the following components)	set, complete mounting board with pre- installed material as noted below for complete turn-key installation and additional consumables (e.g., wires, fuses, battery fuses, combiner and distribution boxes, load centre, earthing system, surge protection devices, etc.) All components shall be pre-installed on a mounting board covering electrical components and consumables. PV modules and batteries are not part of the mounting board, but their cabling and connection must be designed for plug and play usage. lump sum, turn-key installation at site by a qualified technician Documentation for all technical products shall be available	1	pcs
14	Submersible pump system (will be inserted into reservoir)	Submersible Pump, range 500700 W Complete submersible pump kit  - DC submersible water pump  - DC submersible water pump controller  - submersible cable for electrical connection  - flexible water pipes of sufficient length (installation set)  Pump has to be attached to the mounting board at the lowest point with no electrical components below. Electronic equipment has to be protected from accidental water pipe bursts by using transparent shielding. Pumping Head max 15 m Flow Rate min 15 m³/h Water Pipe Length, 2 pcs, min 30 m, One for	1	pcs

		each reservoir. Reservoirs will be installed outside the building for safety reasons. Connection has to be pluggable without tools for setup and removal. Dry Run Protection Sensor. Has to be attached to mounting board Tank Full Sensors, 2 pcs, One for each reservoir. Cable length must be 30m.		
15	Safety water level sensor for safety water reservoirs		2	pcs
16	DC bench power supply (to simulate PV modules)	voltage and current specifications according to both pumps;at least 2 channels; adjustable 0 - 30 VDC; 0 - 3A; 195W;Resolution: Voltage: ≤0.01% + 2mV; Current: ≤0.01% + 250uA	2	pcs
17	Surface Pump (wall mount on mobile work bench)	complete surface pump kit  - DC surface water pump  - DC surface water pump controller  - flexible water pipes of sufficient length (installation set)  - 2 water level sensors (high/low)  - dry running protection	1	pcs
18	Surface Pump Control Unit (wall mount on mobile work bench)	only for reference (must be included in surface pump kit)	0	pcs
19	Surface Pump tubes, pipes, sensors	only for reference (must be included in surface pump kit)	0	pcs
20	Water pressure gauge	according to used water pipes	2	pcs
21	Water reservoir	200 litres with cover	2	pcs
22	Safety water reservoir (water reservoir will stand inside)	PE, must be able to take up all the water from both reservoirs plus safety (volume of one reservoir)	2	pcs
23	Mobile work bench	including RCD with 6 AC outlets, electrically safe and acid resistive coating, dimensions: 1250 x 1970 x 700 mm	1	pcs
24	Acrylic safety housing for surface pump	dimensions must match the surface pump	1	pcs
25	Emergency stop switch for pumps	red emergency stop button on yellow background, surface mounted	1	pcs

26	Relay box with 4mm laboratory safety connectors	plastic box with DIN rail mount to hold 3 relays - 6 red 4mm terminals (32 A rated) with 2.5mm² cable connections to 3 relays - 6 black 4mm terminals (32 A rated) with 2.5mm² cable connections to 3 relays	1	pcs
27	Work board (to be attached to the mobile work bench)	dimensions must match and fit to the mobile work bench, e.g. 1250 x 1000 mm; 20 mm thickness	2	pcs
G	TESTING EQUIPMENT			
	Tools for testing			
	IV-Curve tracer - HT I- V500W	Testing Equipment: IV-Curve Tracer; Isolation tester, Camera, EL-Camera (Electroluminescence), Thermography camera, laboratory power supply		pcs
			1	
1				
	Isolation measurement equipment/ installation tester	Benning PV 1-1 Installations tester kalibriert (ISO) VDE-Norm 0126		pcs
2			1	
	Thermography camera	Image quality with IR resolution of minimum 320 x 240 pixels (with testo SuperResolution technology 640 x 480 pixels)		pcs
3			1	
4	Camera	Technical specifications: Min. 12 MP	1	pcs
5	Electroluminescence camera	Modified Consumer Camera (preferred SLR Camera from Sony: Sony Alpha 7a)	1	pcs

	IR thermometer	Fluke 62 MAX Infrarot-Thermometer Optik 10:1		pcs
			2	
6				
7	Multimeter x2	Fluke 289 FlukeView® Forms Combo Kit	2	pcs
8	Pressure valve	Flux 0.4-10 m³/h, regulate flow rate	1	pcs
9	Flow meter	Min. 0.4 m³/h - 10 m³/h/ Digital output via USB	1	pcs
	Technical testing			
	equipment			
10	Laboratory power supply x2	Technical specifications: 15A, 60V	2	
11	PV modules testing stand	2 PV modules + alum. structure/rack (other already included in and "Tools")	1	pcs
12	Small inverters testing stand	Just price for small inverters, as this can be included in modules testing setup and "Tools"	1	pcs
13	Test Stand Charge Controller	Included in stand-alone/SHS rig and "Tools"	1	pcs
14	Test Stand Batteries	Included in stand-alone/SHS rig and "Tools" + lead-acid battery and 4-Quadranten PV power supply kit	1	pcs
15	Stand-alone/Solar-home- systems testing kit	Costs mainly for building up the rig: akku, micro-inverter, bulbs and small electronic devices	1	pcs
16	PV water pumping testing stand	As part of the Water Pumping outdoor training unit	1	pcs
17	Cable and connectors testing kit	"Tools" should be enough + prices for some cables (as sample)	1	pcs
18	Lighting	For this one the testing and training rig would be the same	1	pcs
19	Material (tools, racking, test stand setup, pipes, cable, safety equipment, spare parts)		1	
20	Microinverter x5		5	
21	Bulbs		1	
22	Computer/office x2		2	

The company selected for installation and commissioning should ensure proper synchronization and integration of the solar system and associated components to enable productive loads and smooth operation.

## Notes:

- 1. The offered PV Modules should comply with the relevant IEC standards, including but not limited to IEC 61215, IEC 61730, UL 61730, IEC 62716 as well as local country's standards.
- 2. All solar components imported to Somalia must comply with the import quality standards for the country.
- 3. Brands mentioned (if any) are indicative only. ISA may consider equivalent brands meeting the specifications.
- 4. Bidders are free to procure items locally within the mentioned country as well.

The company needs to submit relevant documents towards compliance of the above standard.

#### **General Guidance**

- The bidder can source the equipment from anywhere, but the equipment should be of good quality meeting the specifications as listed in the table.
- In case of battery, the bidder can procure it locally where the centre is being established.
- The preferred mode of transportation will be air freight, however economical route needs to be considered. The delivery, commissioning time in the country for all the equipment is maximum 90 days.
- It is bidder's responsibility to arrange labour or technicians for installation of equipment. The cost can be included in the final costing of the equipment.
- The bidder will provide manufacturer's warranty for all the equipment with complete documentation.

#### **B.** Objective

The objective of the assignment is to set up a model solar training and application resource centre (STAR C) lab at the **Somali National University.** 

## C. Scope of Work

- 1. Component A: Supply, installation and Commissioning of the equipment's given in the above table.
- 2. Component B: Training of the Country's staff on Operation and Maintenance practice of the equipment and instruments.
- 3. Component C: Comprehensive Operation and Maintenance for 1 year post commissioning.

The roles and responsibilities of the bidder and ISA are outlined below:

Bidder's Terms of reference:

- Design concepts
- Supply of materials and products
- Provide adequate skilled labour for installation and commissioning
- Construction supervision / contract management
- Quality control plan (QCP) and Safety plan
- Commissioning of project
- Mentoring and training, building operating staff for operation and maintenance
- Operation and Maintenance for first year and optional service plan after the first year

ISA and Country's identified STAR-Cs responsibilities:

- Provide location to install solar panels as per the contract.
- Review for approval design submittals
- Witness inspections and test witnesses to verify attainment of performance requirements
- Make progress payments for any service agreed

- Allow consultants access to STAR-C premises for site visit/energy audit exercise.
- Approve any contracts agreed with the consultant.

#### **Payment Terms**

#### For Component-A (Supply, Installation and Commissioning of the equipment's)

S. No.	<b>Description of Deliverables</b>	Timelines	Release of payment
1	Kick-off meeting with a tentative plan	1 Week	20%
	for supply of material, Installation &		
	Commissioning		
2	Dispatch of material (Document proof	3 Weeks	10%
	of dispatch)	5 Weeks	
3	Successful delivery of material on site.	10 Weeks	50%
4	Successful Installation, Commissioning	12 Weeks	15%
5	After successful operation for 3		5%
	months		

#### Notes:

- i. Transportation cost will be paid at the time of dispatching of the material.
- ii. Custom duty/excise duty will be paid on actual after submission of invoice and proofs.
- iii. Part payments will be allowed for Component-A pricing.

# For Component-B (Training of the Country's staff on Operation and Maintenance practice of the equipment and instruments)

S. No.	Description of Deliverables	Timelines	Release of payment
1	Training of the Country's staff on	Within 2 Weeks after	100%
	Operation and Maintenance	Successful Installation	
	practices	& Commissioning	

## Notes:

i. Training of 3-5 people for maximum 4 days on day-to-day O&M of the equipment's.

## For Component-C (Comprehensive Operation and Maintenance for 1 year post commissioning)

i. Payment will be processed in two tranches, 1<sup>st</sup> tranche at the end of six months after commissioning and 2<sup>nd</sup> Tranche at the end of 12 months after commissioning.

## **Delivery Requirements**

Delivery Requirements		
Delivery date and time  Bidder shall complete the delivery and installation within 90 days from the issuance of Contract.		
Delivery Terms (INCOTERMS 2020)	Delivered at Place	
Customs clearance	☐ Not applicable	
	Shall be done by:	

	☐ Name of organisation (where applicable)
	⊠ Supplier/bidder
	☐ Freight Forwarder
Exact Address(es) of Delivery Location(s)	Somali National University
Distribution of shipping	Bidder responsibility
documents (if using	
freight forwarder)	
Packing Requirements	Safe delivery of supplies, handling will be bidders responsibility
Training on Operations and Maintenance	Within 14 days of delivery and installation
Warranty Period	At least one year
After-sales service and local service support requirements	One year
Preferred Mode of Transport	Air

## NOTES:

- a. The products/goods/parts of machineries must be recalled by the manufacturer/ bidder/ supplier at the manufacturers/ bidder/ suppliers cost if rejected by ISA/ purchaser or end user because of the problems with quality. The supplier/ bidder/ manufacturer will be obliged to replace the products/goods/parts of machineries in question at its own cost with a new one of acceptable quality.
- b. The supplier will be responsible for protection of materials, property and equipment before successful delivery and handover to ISA.
- c. Prices quoted must be inclusive of all costs necessary to supply these items, including delivery, warranty, transport cost, insurance, materials, installation, training and commissioning etc.
- d. OEM of equipment's' can be from any country. However, meeting the technical specifications is mandatory requirement.
- e. Items can be procured locally, within the country. However, bidder shall provide 1 year CMC as per the contract.

## **ANNEX 2: QUOTATION SUBMISSION FORM**

Bidders are requested to complete this form, including the Company Profile and Bidder's Declaration, sign it and return it as part of their quotation along with Annex 3: Technical and Financial Offer. The Bidder shall fill in this form in accordance with the instructions indicated. No alterations to its format shall be permitted and no substitutions shall be accepted.

Name of Bidder:	Click or tap here to enter text.	
RFQ reference:	Click or tap here to enter text.	Date: Click or tap to enter a date.

## **Company Profile**

Item Description	Detail
Legal name of bidder or Lead entity for JVs	Click or tap here to enter text.
Legal Address, City, Country	Click or tap here to enter text.
Website	Click or tap here to enter text.
Year of Registration	Click or tap here to enter text.
Legal structure	Choose an item.
Are you a UNGM registered vendor?	☐ Yes ☐ No If yes, insert UNGM Vendor Number
Quality Assurance Certification (e.g. ISO 9000 or Equivalent) (If yes, provide a Copy of the valid Certificate):	☐ Yes ☐ No
Does your Company hold any accreditation such as ISO 14001 or ISO 14064 or equivalent related to the environment? (If yes, provide a Copy of the valid Certificate):	☐ Yes ☐ No
Does your Company have a written Statement of its Environmental Policy? (If yes, provide a Copy)	☐ Yes ☐ No
Does your organization demonstrate significant commitment to sustainability through some other means, for example internal company policy documents on women empowerment, renewable energies or membership of trade institutions promoting such issues (If yes, provide a Copy)	☐ Yes ☐ No

Is your company a member of the UN Global Compact		☐ Yes ☐ No				
Bank Information		Bank Name: Click or tap here to enter text.				
		Bank Address: Click or tap here to enter text.				
		IBAN: Click or tap here to enter text.				
		SWIFT/BIC: Click or tap here to enter text.				
		Account Currency: Click or tap here to enter text.				
		Bank Account Number: Click or tap here to enter text.				
Previous relevant experience: 3 contracts						
Name of previous	Client & Reference		Contract	Period of activity	Types of activities	
contracts	Contact Details including e-mail		Value		undertaken	

## **Bidder's Declaration**

Yes	No	
		<b>Requirements and Terms and Conditions:</b> I/We have read and fully understand the RFQ, including the RFQ Information and Data, Schedule of Requirements, the General Conditions of Contract, and any Special Conditions of Contract. I/we confirm that the Bidder agrees to be bound by them.
		I/We confirm that the Bidder has the necessary capacity, capability, and necessary licenses to fully meet or exceed the Requirements and will be available to deliver throughout the relevant Contract period.
		<b>Ethics</b> : In submitting this Quote I/we warrant that the bidder: has not entered any improper, illegal, collusive, or anti-competitive arrangements with any Competitor; has not directly or indirectly approached any representative of the Buyer (other than the Point of Contact) to lobby or solicit information in relation to the RFQ; has not attempted to influence, or provide any form of personal inducement, reward, or benefit to any representative of the Buyer.
		I/We confirm to undertake not to engage in proscribed practices, , or any other unethical practice, with the UN or any other party, and to conduct business in a manner that averts any financial, operational, reputational or other undue risk to the UN and we have read the United Nations Supplier Code of Conduct: <a href="https://isolaralliance.org/images/ISA%20Supplier%20Code%20Of%20Conduct 14.4.2023.final%20version.pdf">https://isolaralliance.org/images/ISA%20Supplier%20Code%20Of%20Conduct 14.4.2023.final%20version.pdf</a> and acknowledge that it provides the minimum standards expected of suppliers to the UN.
		Conflict of interest: I/We warrant that the bidder has no actual, potential, or perceived Conflict of Interest in submitting this Quote or entering a Contract to deliver the Requirements. Where a Conflict of Interest arises during the RFQ process the bidder will report it immediately to the Procuring Organisation's Point of Contact.
		<b>Prohibitions, Sanctions:</b> I/We hereby declare that our firm, its affiliates or subsidiaries or employees, including any JV/Consortium members or subcontractors or suppliers for any part of the contract is not under procurement prohibition by the United Nations, including but not limited to prohibitions derived from the Compendium of United Nations Security Council Sanctions Lists and have not been suspended, debarred, sanctioned or otherwise identified as ineligible by any UN Organization or the World Bank Group or any other international Organization.
		<b>Bankruptcy</b> : I/We have not declared bankruptcy, are not involved in bankruptcy or receivership proceedings, and there is no judgment or pending legal action against them that could impair their operations in the foreseeable future.

Yes	No	
		Offer Validity Period: I/We confirm that this Quote, including the price, remains open for acceptance for the
		Offer Validity.
		I/We understand and recognize that you are not bound to accept any Quotation you receive, and we certify
		that the goods offered in our Quotation are new and unused.
		By signing this declaration, the signatory below represents, warrants and agrees that he/she has been
		authorised by the Organization/s to make this declaration on its/their behalf.

Signature:	
Name:	Click or tap here to enter text.
Title:	Click or tap here to enter text.
Date:	Click or tan to enter a date

### **ANNEX 3: TECHNICAL AND FINANCIAL OFFER - GOODS**

Bidders are requested to complete this form, sign it and return it as part of their quotation along with Annex 2 Quotation Submission Form. The Bidder shall fill in this form in accordance with the instructions indicated. No alterations to its format shall be permitted and no substitutions shall be accepted.

Name of Bidder:	Click or tap here to enter text.	
RFQ reference:	RFQ/XXXX/IND 2023	Date: Click or tap to enter a date.

## **Technical Offer**

### **Qualification Criteria**

Please fill this and attach relevant documents. Only quotations of bidders qualifying against the below criteria will be evaluated.

Qualifying Criteria	Yes/No	List of supporting documents
Bidders must have the legal capacity to enter a binding		
contract with ISA and to deliver in the country, or		
through an authorized representative.		
Bidders must have the legal capacity to enter a binding		
contract with ISA and to deliver in the country, or		
through an authorized representative. Company		
registration certificate or any other document proving		
legal entity.		
The bidder must have the experience of supply of solar		
equipment's / hardware components. Submit copy of		
work order or completion certificate		
The bidder must have annual turnover of more than USD		
100,000 - Please attach relevant documents.		

ISA reserves the right to reject the bid if it determines that the selected bidder has not provided the supporting documents against the Qualifying Criteria.

### **Technical Criteria**

Provide the following:

- a brief description of your qualification and capacity that is relevant to the Scope of Works;
- a brief method statement and implementation plan;

Technical offer should encompass detailed specifications, including make, complying standards, relevant test certificate as applicable for each of the component proposed to be supplied by the bidder under the RFQ in line with the table below.

Item	Equipment	Quantity	Detailed Specification	Make/ Model	Complying standard	Period of Warranty
Α	Tools and instruments					
A1	Personal Protective Equipment					
1	Reflective vests					
2	Helmets					
3	Work gloves					
A2	Instruments					
4	Digital multimeter (medium quality)					
5	Spare fuses for above multimeter (medium quality)					
6	Digital multimeter (professional standard)					
7	Spare fuses for above multimeter (professional standard)					
8	Clamp meter (medium quality)					
9	Clamp meter (professional standard)					
10	Insulation resistance tester					

11	Plug-in wattmeter			
12	Hand-held solar irradiance meter			
12	Tranu-field Solar III adiance meter			
13	Infrared thermometer			
14	Solar Pathfinder			
15	Sun path diagrams for the Solar			
	Pathfinder (only if Solar Pathfinder can be procured)			
	can be procured,			
16	Compass			
10	Compass			
А3	Tools			
17	Crimp/termination tools for PV			
	interconnectors			
18	Crimping tool kit & crimps			

19	Electrician's tools kit			
20	Adjustable spanners			
21	Coopporat			
21	Spanner set			
22	Screwdriver set for precision			
	mechanics			
22	Designation of the second			
23	Basic vehicle mechanics tools set			
24	Long tape measures			
25	Lludromotor			
25	Hydrometer			
26	Allen key set			
27	Clipboards			
A4	Extras and spares			

28	Safety harness kit for working at height / on roofs			
29	Replacement batteries for multi- und clamp meters			
30	multimeter special cables (thermocouples, croco clamps, etc.)			
31	Soldering iron/station			
32	Soldering tips			
33	Solder			
34	Multiple socket strip with personal protection			
35	Hot air gun			
36	Schottky Diode 15 A 45 V			
37	Soldering station  Multifunction Tool			
39	Bench power supply			
40	Anti-static pad for work space with earth wall plug			

41	Anti-static wrist band with earthing connection			
В	PV EXERCISE BOARDS			
	PV modules			
1	PV module			
2	PV module			
3	PV module			
4	PV module			
	PV cable connectors			
5	PV module inter-connection connectors (male)			
6	PV module inter-connection connectors (female)			
7	PV module inter-connection connectors (female)			
8	PV module inter-connection connectors (male)			

9	MC4 Y-plug			
	DC exercise boards			
10	Solar charge controller (standard, without MPPT)			
11	Solar charge controller (standard, without MPPT)			
12	Solar charge controller (with MPPT)			
13	Inverter (battery inverter)			
14	DC lamps, 12 V, florescent			
15	DC lamps, 12 V, LED			
16	DC lamps, 12 V halogen			
17	Lamp holders			
18	DC fans			
19	DC/DC converter			

20	DC sockets				
24					
21	DC plugs				
22	Junction boxes				
23	DC miniature circuit breakers				
24	DC miniature circuit breakers				
25	DC miniature circuit breakers				
	AC exercise boards				
26	Consumer unit / fuse board				
20	Consumer unity ruse bourd				
27	Miniature circuit breaker (MCB) AC				
28	Miniature circuit breaker (MCB) AC				
29	Residual current device (RCD)				
L	1	1	1		

30	Socket outlet			
31	Socket outlet			
32	Socket outlet			
32	Socket Gutlet			
33	Plug			
34	Plug			
35	Plug			
36	Connector blocks / terminal strips			
37	Connector blocks / terminal strips			
20	Compostor blocks / towning lating			
38	Connector blocks / terminal strips			
39	Earth blocks			
	Cables, etc.			
40	Flex			
41	Cable			
-				
42	Cabla			
42	Cable			

43	Cable			
44	PV cable / 'solar cable'			
45	Cable			
46	Cable			
40	Cable			
47	Cable			
48	Cable			
49	Cable			
50	Cable			
51	Electrical insulation tape			
	Batteries & accessories			

52	Battery			
	,			
53	Battery terminals (pairs)			
54	Lead-acid batteries			
55	Battery terminals (pairs)			
56	Battery charger			
57	Funnel			
58	Acid pump (hand-driven)			
36	Acid pump (mand-driven)			
59	Work board			
С	HYBRID SYSTEM			
1	PV modules			
	Hybrid inverter			
2				
3	Battery system			
4	Monitoring			
5	BOS-set			
6	Consumables			
7	Consumables			
8	Consumables			
9	Consumables			
10	Mounting			
11	Mounting EPC-service			
12	EPC-Service			
D	SOLAR HOME SYSTEM			
	Solar Home System Installation			
	(made up of the following			
	components)			
1	Solar Charge Controller MPPT			
	John Charge Controller Wiff I			

3	VRLA AGM Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including interconnection, cable, screws, isolator, and cable to Battery Fuse and from Fuse to Inverter> Charge controller  PV Modules Total min 300Wp, Voltage suitable for Charge Controller, Inverter			
4	Roof Mounting Substructure, Aluminium for Metal sheet Roof with wooden Screws for wooden substructure on a training rood			
5	Remote Monitoring Device			
6	DC Load Distribution Box			
7	Inverter			
8	Mounting Board			
	Solar Home System Kit			
9	Solar Home System Kit or Bundle			
9	Solai Home System Kit of Bullule			
10	SHS Solarworx lamps 1W			
10	SHS Solarworx lamps 1W			
10	SHS Solarworx lamps 1W SHS Solarworx 32 inch TV			
10 11 12	SHS Solarworx lamps 1W  SHS Solarworx 32 inch TV  SHS Solarworx fridge  SHS Solarworx Victron PayG Dongle or switch			
10 11 12	SHS Solarworx lamps 1W  SHS Solarworx 32 inch TV  SHS Solarworx fridge  SHS Solarworx Victron PayG Dongle			

1	Solar Street Light Kit		1	ĺ
	Join Street Light Nit			
2	Lamp post for Street Light Kit			
3	Scaffold complete assembly			
	Scarrold complete assembly			
4	Scaffolding Elevator Console with			
	Pulley			
5	Ladder			
	Solar street light indoor			
6	100Wp Solar Street Lighting System,			
0				
	20 W LED light (made up of the			
	following components)			
1 7	Solar Charge Controller MPPT			
7	Solar Charge Controller MPPT			
7	Solar Charge Controller MPPT			
8	VRLA Gel Battery for Cycling Solar			
	VRLA Gel Battery for Cycling Solar applicationsTotal capacity min			
	VRLA Gel Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including			
	VRLA Gel Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including interconnection, cable, screws,			
	VRLA Gel Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including interconnection, cable, screws, isolator, and cable to Battery Fuse			
	VRLA Gel Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including interconnection, cable, screws, isolator, and cable to Battery Fuse and from Fuse to Inverter> Charge			
	VRLA Gel Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including interconnection, cable, screws, isolator, and cable to Battery Fuse			
	VRLA Gel Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including interconnection, cable, screws, isolator, and cable to Battery Fuse and from Fuse to Inverter> Charge controller  DC bench power supply (to simulate			
8	VRLA Gel Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including interconnection, cable, screws, isolator, and cable to Battery Fuse and from Fuse to Inverter> Charge controller			
8	VRLA Gel Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including interconnection, cable, screws, isolator, and cable to Battery Fuse and from Fuse to Inverter> Charge controller  DC bench power supply (to simulate			
8	VRLA Gel Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including interconnection, cable, screws, isolator, and cable to Battery Fuse and from Fuse to Inverter> Charge controller  DC bench power supply (to simulate			
9	VRLA Gel Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including interconnection, cable, screws, isolator, and cable to Battery Fuse and from Fuse to Inverter> Charge controller  DC bench power supply (to simulate PV modules)			
8	VRLA Gel Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including interconnection, cable, screws, isolator, and cable to Battery Fuse and from Fuse to Inverter> Charge controller  DC bench power supply (to simulate			
9	VRLA Gel Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including interconnection, cable, screws, isolator, and cable to Battery Fuse and from Fuse to Inverter> Charge controller  DC bench power supply (to simulate PV modules)			
9 10 11	VRLA Gel Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including interconnection, cable, screws, isolator, and cable to Battery Fuse and from Fuse to Inverter> Charge controller  DC bench power supply (to simulate PV modules)  Remote Monitoring Device  DC Load Distribution Box			
9	VRLA Gel Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including interconnection, cable, screws, isolator, and cable to Battery Fuse and from Fuse to Inverter> Charge controller  DC bench power supply (to simulate PV modules)  Remote Monitoring Device			
9 10 11	VRLA Gel Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including interconnection, cable, screws, isolator, and cable to Battery Fuse and from Fuse to Inverter> Charge controller  DC bench power supply (to simulate PV modules)  Remote Monitoring Device  DC Load Distribution Box			
9 10 11	VRLA Gel Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including interconnection, cable, screws, isolator, and cable to Battery Fuse and from Fuse to Inverter> Charge controller  DC bench power supply (to simulate PV modules)  Remote Monitoring Device  DC Load Distribution Box			

13	LED lamp			
14	Twilight Switch /w Relay (not mandatory if already included in			
	LED Lamp)			
15	Movement Sensor (not mandatory if already included in LED Lamp)			
16	Mounting Board			
17	Mobile work bench			
_				
F	SOLAR WATER PUMPING SYSTEM OUTDOOR and INDOOR			
	Solar water pumping outdoor			
1	Reservoir			
2	Flange for reservoir connection with outlet tap			
3	Water pipe DN 50			
4	Surface pump complete kit			
5	Submersible pump complete kit			

6	Cast resin sleeve for submersible pump electric connection			
7	Submersible cable to train cast resin application			
8	Water pressure gauge			
9	Closing valve			
10	Water flow meter			
11	PV Modules Total min 300Wp, Voltage suitable for Charge Controller, Inverter AS REFERENCE FOR THE PV MODULES INCLUDED IN PUMP KITS ABOVE!			
12	Roof Mounting Substructure, Aluminium for Metal sheet Roof with wooden Screws for wooden substructure on a training rood			
	Solar water pumping indoor			
13	500700 W Solar Water Pumping System (made up of the following components)			
14	Submersible pump system (will be inserted into reservoir)			
15	Safety water level sensor for safety water reservoirs			
16	DC bench power supply (to simulate PV modules)			
17	Surface Pump (wall mount on mobile work bench)			
18	Surface Pump Control Unit (wall mount on mobile work bench)			
19	Surface Pump tubes, pipes, sensors			
20	Water pressure gauge			
21	Water reservoir			

22	Safety water reservoir (water reservoir will stand inside)			
23	Mobile work bench			
24	Acrylic safety housing for surface pump			
25	Emergency stop switch for pumps			
26	Relay box with 4mm laboratory safety connectors			
27	Work board (to be attached to the mobile work bench)			
G	TESTING EQUIPMENT			
	Tools for testing			
1	IV-Curve tracer - HT I-V500W			
2	Isolation measurement equipment/installation tester			
3	Thermography camera			
4	Camera			
5	Electroluminescence camera			
6	IR thermometer			
7	Multimeter x2			
8	Pressure valve			
9	Flow meter			
	Technical testing equipment			
10	Laboratory power supply x2			
11	PV modules testing stand			
12	Small inverters testing stand			
13	Test Stand Charge Controller			
14	Test Stand Batteries			
15	Stand-alone/Solar-home-systems testing kit			

16	6 PV water pumping testing stand		
17	7 Cable and connectors testing kit		
18	8 Lighting		
19	9 Material (tools, racking, test stand setup, pipes, cable, safety equipment, spare parts)		
20	0 Microinverter x5		
21	1 Bulbs		
22	2 Computer/office x2		

The submission of proposal should highlight in subject line "SITC for equipment in Somalia"

# **Financial Offer**

Financial offer should encompass the quantity and price as applicable for each of the component propose
to be supplied by the bidder under the RFQ in line with the table below:

Submission for the Country...... (fill the country name)

Ite m	Equipment	Specification EN	Quantity	Unit Price (USD)	Total Price (USD)
Α	Tools and instruments				
A1	Personal Protective	Specification			
	Equipment				
1	Reflective vests	Reflective vests			
2	Helmets	Helmets			
3	Work gloves	Work gloves			
A2	Instruments	Specification			
4	Digital multimeter (medium quality)	TRMS values, capable of measuring AC (750 V) & DC (1000 V) voltages, DC current 10 A, continuity/resistance, fused for current measurements, overvoltage CAT III 1,000 V and CAT IV 600 V. Lower-cost instruments are suitable for work board exercises			
5	Spare fuses for above multimeter (medium quality)	30 of each type of fuse in multimeter			
6	Digital multimeter (professional standard)	TRMS values, Capable of measuring 1000 V AC/DC voltages, DC current 10 A, continuity/resistance, fused for current measurements, overvoltage CAT III 1,000 V and CAT IV 600 V, temperature probe, test leads and accessories This needs to be a 'professional standard' instrument such as the Fluke 179 or similar			
7	Spare fuses for above multimeter (professional standard)	5 of each type of fuse in multimeter			

8	Clamp meter (medium quality)	Capable of measuring AC & DC (600 V) voltages, DC and AC current ranges 40 A / 400 A, continuity/resistance, overvoltage CAT III 600 V. Lower-cost instruments are suitable for work board exercises		
9	Clamp meter (professional standard)	TRMS values, capable of measuring AC & DC (600 V) voltages, DC and AC current ranges 40 A / 400 A, continuity/resistance, overvoltage CAT III 600 V and CAT IV 300 V. This needs to be a 'professional standard' instrument such as the Fluke 325 or similar		
10	Insulation resistance tester	Capable of measuring insulation resistance at 250 V, 500 V and 1000 V, isolations-resistance measurement to 20 G $\Omega$ , resistance measurement 0,01 $\Omega$ - 20 k $\Omega$ , AC voltage measurement 0 - 500 V AC, overvoltage CAT IV 600 V		
11	Plug-in wattmeter	To fit AC sockets being used in country (Type C, D or G sockets, the most common one to be selected); capable of measuring appliance power consumption (W), energy (kWh) and cost of electricity consumed		
12	Hand-held solar irradiance meter	Capable of measuring solar irradiation, hand- held, 0 - 2000 W/m2 range, resolution 1 W/m², digital display		
13	Infrared thermometer	Hand held laser Infrared thermometer, -20 to 100 ° C minimum range, digital display		

15	Solar Pathfinder  Sun path diagrams for the Solar Pathfinder (only if Solar Pathfinder can be procured)  Compass	The Solar Pathfinder is the instrument specified. It is relatively low-cost, does not require batteries and is ideal for didactic purposes. To be supplied with tripod.  For correct latitudes: Available from manufacturer/supplier of Solar Pathfinder  Basic, low cost, pocket		
10	Compass	size compass, of type used by walkers		
А3	Tools	Specification		
17	Crimp/termination tools for PV interconnectors	For MC4 PV module connectors, 4-6mm <sup>2</sup> wires (minimum range)		
18	Crimping tool kit & crimps	Crimping tool kit & supply of 800 min. crimps/lugs. For insulated cable lugs from 0.5 to 6 mm² (red-blue-yellow) and non-insulated cable lugs from 1.5 to 10 mm², VDE certified		
19	Electrician's tools kit	Set of electricians' insulated hand tools, screwdrivers, pliers, cable cutter, cable stripper, 1000 V insulation, standard IEC EN 60900		
20	Adjustable spanners	Maximum opening: 30 mm		
21	Spanner set	For nuts and bolts widths 6 - 22 mm (recommended range)		
22	Screwdriver set for precision mechanics	For single slot and Philipps screws: 6 different standard sizes		
23	Basic vehicle mechanics tools set	Basic set, socket set, suitable for work on cars and motor cycles, metric		

24	Long tape measures	Also called builder/surveyor's tapes, 20m or more, fibreglass tape (not steel), metric		
25	Hydrometer	For measuring battery electrolyte specific gravity		
26	Allen key set	Key sizes : 1.5 - 10 mm approx.		
27	Clipboards	Suitable for outdoor use, A4, perspex		
A4	Extras and spares	Specification		
28	Safety harness kit for working at height / on roofs	Complete kit. including harness, fall arrest lanyard, D rings, and packing case/rucksack		
29	Replacement batteries for multi- und clamp meters	spare part for multimeters, check requirements of procured meters and provide multiple spare batteries of all required types		
30	multimeter special cables (thermocouples, croco clamps, etc.)	only if not supplied with original equipment		
31	Soldering iron/station	60W, 230 Volts		
32	Soldering tips	according to soldering station		
33	Solder	100g roll, lead-free		
34	Multiple socket strip with personal protection	5+ sockets		
35	Hot air gun			
36	Schottky Diode 15 A 45 V	THT axial bypass diode, 15A, 45V		
37	Soldering station	Adjustable temperature range (100°C-450°C), 70W, 5 different solder tips, tip stand and sponge		

38	Multifunction Tool	Battery powered, fully variable speed 5.000 35.000 1/min, at least with 30 accessories, 12VDC, carry case		
39	Bench power supply	1-channel, adjustable voltage 0VDC-40VDC, display, adjustable current 0A-10A, 150W minimum		
40	Anti-static pad for work space with earth wall plug	heat-resistant, DIN EN 61340-5-1 , 0.5m x 0.3m minimum		
41	Anti-static wrist band with earthing connection	anti-static wrist band with cable and compatible with pad		
В	PV EXERCISE BOARDS			
	PV modules	Specification		
1	PV module	PV module, polycrystalline, 36 cells, 120 Wp approx., 20 Voc approx., 36 cells, aluminium frame, junction box not pre- cabled (openable, not sealed), product certification IEC 61215		
2	PV module	PV module, monocrystalline, 36 cells, 120 Wp approx., 20 Voc approx., 36 cells, aluminium frame, junction box not pre- cabled (openable, not sealed), product certification IEC 61215		
3	PV module	Mono or polycrystalline, 150 Wp approx., 40 Voc approx., 72 cells, aluminium frame, junction box not pre- cabled (openable, not sealed), product certification IEC 61215		

4	PV module	20 -50 Wp (small), monocrystalline and polycrystalline, 20 Voc approx., 36 cells, aluminium frame, junction box not pre- cabled (openable, not sealed), product certification IEC 61215, a selection of different types		
	PV cable connectors	Specification		
5	PV module inter- connection connectors (male)	MC4 male connectors for 4 mm <sup>2</sup> solar cable. and suitable for above crimp/termination tool, IP65, 30 A, 1000 DC		
6	PV module inter- connection connectors (female)	MC4 female connectors for 4 mm <sup>2</sup> solar cable. and suitable for above crimp/termination tool, IP65, 30 A, 1000 DC		
7	PV module inter- connection connectors (female)	MC-4 compatible PV connectors, male, which do not require specialised tools, for 4 mm <sup>2</sup> solar cable, IP65, 30 A, 1000 DC		
8	PV module inter- connection connectors (male)	MC-4 compatible PV connectors, female, which do not require specialised tools, for 4 mm² solar cable, IP65, 30 A, 1000 DC		
9	MC4 Y-plug	MC4 compatible Y- connector for parallel connection of PV modules		
	DC exercise boards	Specification		
10	Solar charge controller (standard, without MPPT)	10A module current / 10A load current minimum, PWM, 12/24 V, no MPPT, LED (3 indicating battery state of charge) or LC display, cable input/output terminals for 6 mm² cable min., for lead-acid		

		batteries, overload		
		protection, low voltage		
		disconnect, reverse		
		polarity protection,		
		temperature		
		compensation, open		
		circuit protection when		
		not connected to		
		battery, IP 20 min., 2-		
		year manufacturer's		
		warranty		
11	Solar charge controller	20A solar module current		
	(standard, without MPPT)	/ 20A load current		
		minimum, other specs as		
		above		
12	Solar charge controller	25 A min. approx.		
	(with MPPT)	(in/out), 12/24 V, with		
		MPPT range 17 V 100+		
		V (34 V 100+ V		
		approx.), LC display,		
		cable input/output		
		terminals for 10 mm <sup>2</sup>		
		cable min., for lead-acid		
		batteries, overload		
		protection, low voltage		
		disconnect (deep		
		discharge protection),		
		regular equalisation		
		charge, overcharge		
		protection, reverse		
		polarity protection,		
		temperature		
		compensation, open		
		circuit protection when		
		not connected to		
		battery, IP 20 min.		
13	Inverter (battery inverter)	12 V DC input, from 220 -	 	
		240 V 50 Hz power		
		output, 200 - 500 W (200		
		- 500 VA continuous		
		power), pure sine wave,		
		IP 20 min, overload and		
		short circuit protection,		
		reverse polarity		
		protection as internal		
		fuse, deep discharge		
		battery protection, to be		
		sourced from a supplier		
		of equipment for PV		
		systems and		
		recommended by that PV		

		supplier for use in off- grid PV systems (not a cheap inverter of the type used in motor vehicles), not to contain integrated solar charge controller  If possible provide inverters from 2 different manufacturers		
14	DC lamps, 12 V, florescent	12 V, florescent lamps with replaceable bulb/tube 3 x 7 W 3 x 9 W 3 x 11 W		
15	DC lamps, 12 V, LED	12 V DC, LED, 2 W, E27, 200 lumens min., warm white various wattage, e.g. 3 x 5 W 3 x 10 W 3 x 15 W		
16	DC lamps, 12 V halogen	12V, halogen, with reflectors, selection between 10W and 40W		
17	Lamp holders	E 27 lamp holder, plastic, heavy duty, for surface mounting on work board		
18	DC fans	12 V DC desk fan. 10 W min., 20 W max.		
19	DC/DC converter	DC/DC converter, 12 V to 24 V, 1,5 A minimum output		
20	DC sockets	Socket outlet for 12/24 V DC, for surface mounting on work board		
21	DC plugs	DC plugs to fit above DC sockets		

22	Junction boxes	100 x 100 x 40 mm (LxWxH) approx., surface mounting (for work board)		
23	DC miniature circuit breakers	DC miniature circuit breaker, 1-pole, 80VDC, 6A tripping current, 1 pole, suitable for DIN rail mounting		
24	DC miniature circuit breakers	DC miniature circuit breaker, 1-pole, 80VDC, 10A or 16A tripping current, 1 pole, suitable for DIN rail mounting		
25	DC miniature circuit breakers	DC miniature circuit breaker, 1-pole, 80VDC, 40A or 50A tripping current, 1 pole, suitable for DIN rail mounting		
	AC exercise boards	Specification		
26	Consumer unit / fuse board	To fit DP main switch and 2 - 3 MCBs and E terminal, for 220 - 240 V 50/60 Hz power supply, IP65		
27	Miniature circuit breaker (MCB) AC	Single-pole, 6A, Type B, 220 - 240 V 50/60 Hz, to fit above consumer unit / fuse board		
28	Miniature circuit breaker (MCB) AC	Single-pole, 16A, Type B, 220 - 240 V 50/60 Hz, to fit above consumer unit / fuse board		
29	Residual current device (RCD)	Type A 25A 30mA RCD, 220 - 240 V 50/60 Hz, to fit above consumer unit / fuse board		
30	Socket outlet	Type C 230 V, 2 pole excl. Grounding surface mounted (incl box for surface mounting on board), indoor use, IP22 or IP2X min.		

31	Socket outlet	Type D 230 V, 3 pole incl			
		grounding			
		surface mounted (incl			
		box for surface mounting			
		on board), indoor use,			
22	Coolean author	IP22 or IP2X min			
32	Socket outlet	Type G			
		230 V, 3 pole incl			
		grounding surface mounted (incl			
		box for surface mounting			
		on board), indoor use,			
		IP22 or IP2X min.			
33	Plug	Type C, to fit above			
	l lug	sockets			
34	Plug	Type D, to fit above			
•	1.05	sockets			
35	Plug	Type G, to fit above			
		sockets			
36	Connector blocks /	Screw terminal strip, 3A,			
	terminal strips	400VAC, for 2.5 mm2			
	·	cable			
		(10-12 connector blocks			
		per strip, 240 blocks in			
		total)			
37	Connector blocks /	Screw terminal strip, 6A,			
	terminal strips	400VAC, for 4 mm2 cable			
		(10-12 connector blocks			
		per strip, 240 blocks in			
		total)			
38	Connector blocks /	Screw terminal strip,			
	terminal strips	16A, 400VAC, for 6 mm2			
		cable			
		(10-12 connector blocks			
		per strip, 240 blocks in			
20	Fouth blocks	total)			
39	Earth blocks	4-Way Earth Block			
		Nickel-plated, Suitable for 16-25mm <sup>2</sup> Cables,			
		Brass Construction			
	Cables, etc.	Specification			
40	Flex	1.5 mm2 flexible cable			
40	I ICA	for connecting			
		appliances to plugs, 3-			
		core incl. PE), very			
		flexible, copper. PVC			
		sheathed, H05-VVF, 50 m			
		roll			
	<u>l</u>	I	l	<u> </u>	

41	Cable	1.5mm2, 2-core (no PE), multi-stranded, very flexible, copper, PVC sheathed, H05-VVF, 50 m roll		
42	Cable	2.5mm2, 2-core (no PE), multi-stranded, very flexible, copper, PVC sheathed, H05-VVF, 100 m roll		
43	Cable	2.5 mm2 flexible cable for connecting appliances to plugs, 3-core incl. PE), very flexible, copper. PVC sheathed, H05-VVF, 50 m roll		
44	PV cable / 'solar cable'	4 mm2, double insulated, single-core, UV protected, cable specified for the interconnection of PV modules, fine multistranded, copper, temperature rating -40°C -90°C, 1000 DC, Class II (double insulated), halogen free, flame resistant, 100 m roll		
45	Cable	6 mm2 single-core, fine multi-stranded, PVC, red, very flexible, copper, unsheathed, H07V-K 100 m red roll		
46	Cable	6 mm2 single-core, fine multi-stranded, PVC, red, very flexible, copper, unsheathed, H07V-K 100 m black roll		
47	Cable	6 mm2 single-core, fine multi-stranded, PVC, red, very flexible, copper, unsheathed, H07V-K 100 m yellow-green roll		
48	Cable	10 mm2 single-core, fine multi-stranded, PVC, red, very flexible, copper, unsheathed, H07V-K 100 m red roll		

49	Cable	10 mm2 single-core, fine multi-stranded, PVC, red, very flexible, copper, unsheathed, H07V-K 100 m black roll		
50	Cable	10 mm2 single-core, fine multi-stranded, PVC, red, very flexible, copper, unsheathed, H07V-K 100 m yellow-green roll		
51	Electrical insulation tape	25 m length rolls, 20 mm width, approx., max heat resistant temperature 90 °C 5 x red 10 x black 5 x blue 5 x yellow/green		
	Batteries & accessories	Specification		
52	Battery	12 V lead gel, 60 - 90Ah, sealed, maintenance- free, 'solar batteries'		
53	Battery terminals (pairs)	To fit above battery		
54	Lead-acid batteries	12 V lead-acid, 60 - 90Ah, flooded, 'solar batteries', dry, to be filled with supplied acid at site		
55	Battery terminals (pairs)	To fit above battery		
56	Battery charger	Suitable for charging sealed 12 V 100 Ah lead-acid battery, from 220 - 240 V 50/60 Hz power supply, charging rate 0.8 A / 3.6 A, robust quality, IP65		
57	Funnel	For safely pouring distilled water into batteries, resistant to acids		
58	Acid pump (hand-driven)	Device for safely filling a battery with acid, for demonstration purposes mainly		
59	Work board	1 x 1.5 m approx., thickness 20-25 mm, wood or wood composite, suitable for firmly fixing electrical		

		components to it via		
		wood screws		
С	HYBRID SYSTEM			
		300+ W each, mono- or		
		polycrystalline, IEC		
1	PV modules	certified		
		-Should have the		
		capacity to charge the battery bank from PV		
		solar and Electricity with		
		option of priority setting.		
		- Three-phase connection		
		(single-phase optional if		
		three-phase system not		
		common)		
		- 5000 W AC output,		
		capable to provide		
		backup power in case of		
	Hybrid inverter	grid-failure - Min. 5000 W PV power		
2	Trybria inverter	to be connected		
		Cell chemistry: LiFePo4		
		- Min. 4000 Wh usable		
		storage capacity at 100%		
		DOD)		
		- Min. 4000 cycles		
		- system voltage and		
		integrated BMS compatible with the		
		installed battery (or		
		hybrid) inverter (certified		
		by manufacturer of		
3	Battery system	inverter)		
		If not included as a		
		functionality of the		
		battery inverter (or		
		hybrid inverter), provide		
		a separate monitoring system that monitors the		
		main system parameters		
		and sends them to the		
		manufacturer's data		
4	Monitoring	portal.		
		set to include all wires,		
		connectors, distribution		
_	DOC ant	boxes, switchgear, fuses,		
5	BOS-set	installation material to		

		into anata a falla.		
		integrate a fully		
		operational system		
		4mm <sup>2</sup> DC solar cable:		
		double-insulated, UV-		
		resistant, single core,		
6	Consumables	black		
		DC-connectors: MC4,		
		Sunclix or similar for		
7	Consumables	4mm² cable, male		
		DC-connectors: MC4,		
		Sunclix or similar for		
8	Consumables	4mm² cable, female		
		Cable ties, 20 cm, UV-		
9	Consumables	resistant		
		Ground-mounted		
		mounting system for 20		
		solar modules of the		
		model offered in this bid		
10	Mounting	(item 1)		
		Concrete ballast for		
		mounting system		
11	Mounting	foundation		
		Concept, engineering,		
		procurement, shipping,		
		installation, and		
		commissioning of hybrid		
		system		
		- to include a complete		
		set of system		
		documentation		
		(manuals, datasheets,		
		SLD, wiring diagrams,		
12	EPC-service	etc.)		
D	SOLAR HOME SYSTEM			
	Solar Home System	PV = min. 300Wp		
	Installation (made up of	Inverter = min. 500W		
	the following components)	nom.		
	the following components,	Charge controller if		
		Inverter does not		
		include charge controller		
		Battery display required		
		showing SoC in %,		
		Ampere in/out Battery		
		Voltage, etc.		
		Battery = min. 2.4kWh		
		@c10		
		set, complete mounting		
		board with pre-installed		
		material as noted below		
		for complete turn-key		
		ioi compicte turn-key		

		installation and additional consumables (e.g., wires, fuses, battery fuses, combiner and distribution boxes, load centre, earthing system, surge protection devices, etc.) lump sum, turn-key installation at site by a qualified technician Documentation for all technical products shall be available		
1	Solar Charge Controller	Nominal Power range		
	MPPT	400 W		
		Nominal Voltage (PV Input) max 42 VDC		
		(if designed as 24 VDC		
		system a DC/DC		
		converter will be needed		
		to ensure that standard		
		12 VDC appliances/loads		
		can be used. Converter		
		can be included into load		
		distribution box if cooling		
		is sufficient under load.)		
		Nominal PV Input		
		Current range 520 A		
		Nominal Voltage (Load		
		Output) 12 VDC		
		Nominal Current (Load Output) min 25 A		
		Nominal Battery Voltage		
		range 1224 VDC		
		(autodetect feature		
		mandatory)		
		Operating Temperature		
		range 050 °C		
		MPPT Technology		
		3-Way Battery Charging		
		Profile or better (battery		
		voltage setpoints		
		according to used		
		battery chemistry in 2.0) IP Class		
		Overcharging Protection,		
		adapted to batteries		
		offered		
		Charging Profile, adapted		
		to batteries offered		

I	I		1	İ	]
		Overload Protection (the			
		solar charge controller			
		must be able to handle			
		the situation when a			
		battery is not being			
		connected while PV is			
		already providing power			
		to it)			
		Over-temperature			
		Protection			
		Over-voltage Protection			
		Short Circuit Protection			
		Battery Temperature			
		Compensation (if not			
		available a Battery			
		Temperature Sensor is			
		mandatory)			
		Reverse Polarity			
		Protection on PV and			
		battery terminals (A			
		reverse polarity event			
		shall be resettable			
		without replacing blown			
		fuses. MCBs are			
		preferred but Polyfuses			
		or Crowbar circuit might			
		be an option. If not			
		provided by the charge			
		controller it has to be			
		provided by an external			
		circuit or device. Internal			
		fuses can't be changed			
		locally and will result in			
		unusable equipment)			
		Status Display, Soc in %			
2	VRLA AGM Battery for	Nominal Voltage 12 VDC			
	Cycling Solar	Nominal Capacity (C10)			
	applicationsTotal capacity	min 100 Ah Charge			
	min 2.4kWh @ c10	Cycles at 50% DoD min			
	including interconnection,	1400 Maintenance Free,			
	cable, screws, isolator, and	AGM (has to be a solar			
	cable to Battery Fuse and	battery suitable for daily			
	from Fuse to Inverter>	dis/charge cycles)DC			
	Charge controller	Battery Fuse			
3	PV Modules	PV saline protection (IEC			
	Total min 300Wp, Voltage	61701) if location is close			
	suitable for Charge	to the sea			
	Controller, Inverter	Nominal Power per PV			
		Module min 150 W			
		(when using multiple PV			
		Modules they have to be			
		, , , , , , , , , , , , , , , , , , , ,		1	1

		the same manufacturer and model) Open Circuit Voltage (STC) max 42 VDC Bypass diodes min 3 Reverse Current min 15 A Voltage Capability min 1000 VDC IP Class Junction Box min IP65 Temperature Range range -4085°C Cell Efficiency min 18% Power Tolerance max 5% MC4 Compatible Connectors Monocrystalline Technology		
4	Roof Mounting Substructure, Aluminium for Metal sheet Roof with wooden Screws for wooden substructure on a training rood			
5	Remote Monitoring Device	compatible with solar charge controller unit or Inverter can be wireless (Bluetooth, Wi-Fi) or wired. When wired it has to be USB compliant. If this can be only achieved with a converter it needs to be provided and documented. Compatible with PC (MS Windows) or Android Smartphone		
6	DC Load Distribution Box	Nominal voltage 12 VDC DC Connectors female 5.5/2.1 mm, 2 pcs min 3 A DC Connectors female 5.5/2.5 mm, 2 pcs min 3 A DC Connectors female 4mm safety terminals, 2 pcs min 16 A compatible with 4mm safety cables		

1	I	connector	İ	İ
		DC Connectors female		
		USB type A, 1 pcs min 0.5		
		A can also be provided		
		by solar charge controller		
		if available		
		DC Connectors female		
		USB type A, 1 pcs min 1.5		
		A can also be provided		
		by solar charge controller		
		if available		
7	Inverter	"Nominal Power at 20°,		
		Suitable for humidity >		
		80 % " max 500 W		
		Nominal Voltage Input		
		12 VDC		
		Nominal Voltage Output		
		range 220240 VAC one		
		IEC Type F outlet is		
		sufficient but adapter for		
		Type M must be		
		provided		
		Nominal Frequency 50		
		Hz		
		Nominal Continuous		
		Output Current min 1.4 A		
		Nominal Peak Output		
		Current min 3 A		
		True Sine Wave		
		Dedicated Power Switch		
		Overload Protection		
		Over-temperature		
		Protection		
		Over-voltage Protection		
		Short Circuit Protection		
8	Mounting Board	all components besides		
	<b>3 3 3 3</b>	PV modules and		
		batteries shall be		
		installed on a mounting		
		board		
		Dimensions: Width max		
		12 m, depth max 0.5 m		
		including installed		
		components on		
		mounting structure,		
		Height max 11.5 m		
		Material, Coating and		
		Grounding as defined by		
		manufacturer and local		
		rules		
	Solar Home System Kit	. 5.100		
	Join Home System Rit			

9	Solar Home System Kit or Bundle	Verasol Certification, Lithium Iron Phosphate Battery, GSM (mobile network) remote monitoring, PAYGO integration, MPPT controller, PV input power up to 100W,		
10	SHS Solarworx lamps 1W			
11	SHS Solarworx 32 inch TV			
12	SHS Solarworx fridge			
13	SHS Solarworx Victron PayG Dongle or switch			
E	SOLAR STREET LIGHT			
	Solar street light outdoor			
1	Solar Street Light Kit	Park lamp for public areas and paths, 12W high efficiency LEDs, 1620 lumens, incl. lamp bracket, module mounting structure, top of pole mount battery box, solar charge controller with time program function, 80Wp module, 60Ah sealed battery		
2	Lamp post for Street Light Kit	lamp post 5 metres heigh with accessories for ground assembly, corrosion safe (anodized)		
3	Scaffold complete assembly	TÜV certified; 5,30 m working height, 200 kg/m² load according to DIN EN 1004-1; movable with castors		
4	Scaffolding Elevator Console with Pulley	compatible with scaffolding system, load		

		PV modules to train part exchange		
5	Ladder	6 m working height with stair function, aluminium, must withstand up to 150kg		
	Solar street light indoor			
6	100Wp Solar Street Lighting System, 20 W LED light (made up of the following components)	set, complete mounting board with pre-installed material as noted below for complete turn-key installation and additional consumables (e.g., wires, fuses, battery fuses, combiner and distribution boxes, load centre, earthing system, surge protection devices, etc.) lump sum, turn-key installation at site by a qualified technician Documentation for all technical products shall		
7	Solar Charge Controller MPPT	be available  Nominal Power range 200 W  Nominal Voltage (PV Input) max 42 VDC (if designed as 24 VDC system a DC/DC converter will be needed to ensure that standard 12 VDC appliances/loads can be used. Converter can be included into load distribution box if cooling is sufficient under load.) Nominal PV Input Current range 515 A Nominal Voltage (Load Output) 12 VDC Nominal Current (Load Output) min 10 A Nominal Battery Voltage range 1224 VDC (autodetect feature mandatory) Operating Temperature		

1	ı ı	1
range 050 °C		
MPPT Technology		
3-Way Battery Charging		
Profile or better (battery		
voltage setpoints		
according to used		
battery chemistry in 2.0)		
IP Class		
Overcharging Protection,		
adapted to batteries		
offered		
Charging Profile, adapted		
to batteries offered		
Overload Protection (the		
solar charge controller		
must be able to handle		
the situation when a		
battery is not being		
connected while PV is		
already providing power		
to it)		
Over-temperature		
Protection		
Over-voltage Protection		
Short Circuit Protection		
Battery Temperature		
Compensation (if not		
available a Battery		
Temperature Sensor is		
mandatory)		
Reverse Polarity		
Protection on PV and		
battery terminals (A		
reverse polarity event		
shall be resettable		
without replacing blown		
fuses. MCBs are		
preferred but Polyfused		
or Crowbar circuit might		
be an option. If not		
provided by the charge		
controller it has to be		
provided by an external		
circuit or device. Internal		
fuses can't be changed		
locally and will result in		
unusable equipment)		
Status Display, Soc in %		

8	VRLA Gel Battery for Cycling Solar applicationsTotal capacity min 2.4kWh @ c10 including interconnection, cable, screws, isolator, and cable to Battery Fuse and from Fuse to Inverter> Charge controller	Nominal Voltage 12 VDC Nominal Capacity (C10) min 50 Ah Charge Cycles at 50% DoD min 1400 Maintenance Free (has to be a solar battery suitable for daily dis/charge cycles)DC Battery Fuse		
9	DC bench power supply (to simulate PV modules)	at least 2 channels; adjustable 0 - 30 VDC; 0 - 3A; 195W; Resolution: Voltage: ≤0.01% + 2mV; Current: ≤0.01% + 250uA		
10	Remote Monitoring Device	compatible with solar charge controller unit or Inverter can be wireless (Bluetooth, Wi-Fi33) or wired. When wired it has to be USB compliant. If this can be only achieved with a converter it needs to be provided and documented. Compatible with PC (MS Windows) or Android Smartphone		
11	DC Load Distribution Box	Nominal voltage 12 VDC DC Connectors female 5.5/2.1 mm, 2 pcs min 3 A DC Connectors female 5.5/2.5 mm, 2 pcs min 3 A DC Connectors female 4mm safety terminals, 2 pcs min 16 A compatible with 4mm safety cables connector DC Connectors female USB type A, 1 pcs min 0.5 A can also be provided by solar charge controller if available DC Connectors female USB type A, 1 pcs min 1.5 A can also be provided		

1 1	I	by solar charge controller		
		if available		
12	LED lamp	2x60cm tube, 20-26VDC,		
12		920mA, 22W, 4000K,		
		2200lm, G13, IP22		
13	LED lamp	Nominal Power, range 20		
	223 141119	W		
		Nominal Voltage Input		
		12 VDC		
		Luminous Flux min 5000		
		Im heat dissipation of the		
		lamp shall not affect		
		other components on		
		the mounting board.		
		Colour Temperature min		
		5500 K		
		Radiation Angle min 120°		
		lamp screen shall be		
		parallel to the floor (90°		
		angle between mounting		
		board in upright position		
		and lamp screen) so that		
		blinding of personnel is		
		prevented		
		Working Life min 25,000		
		h		
		On/Off Cycles min		
		100,000		
		Temperature Range,		
		range -2065°C		
		IP Class min IP65		
		Material Aluminium and		
		Glass		
		Lamp Post or mounting		
		bracket for board		
		mounting must be		
		included (negotiable if		
		lamp itself already covers		
		this by design)		
		Length of LED Lamp and		
		Lamp Post max 1 m (may		
		exceed mounting board		
		dimensions but shall be		
	T This is a control of the control	removable for transport)		
14	Twilight Switch /w Relay	Nominal Voltage 12 VDC		
	(not mandatory if already	Nominal Switching		
	included in LED Lamp)	Power min 30 W		
		Switching Capability		
		Power according to		
		selected LED lamp in 6.0		

		(must switch LED lamp safely with enough headroom power)		
15	Movement Sensor (not mandatory if already included in LED Lamp)	detection angle: 180°, programmable twilight and switching time, IP44, 12-24 V		
16	Mounting Board	Dimensions: Width max 12 m, depth max 0.5 m including installed components on mounting structure, Height max 11.5 m Material, Coating and Grounding as defined by manufacturer and local rules		
17	Mobile work bench	including RCD with 6 AC outlets, electrically safe and acid resistive coating, dimensions: 1250 x 1970 x 700 mm		
F	SOLAR WATER PUMPING SYSTEM OUTDOOR and INDOOR			
	Solar water pumping outdoor			
1	Reservoir	water will be pumped from one reservoir to the other and vice versa using two pumps Volume min 1000 litres (1m³) Material Non-Corrosive Big Top Opening Opening Valve at the Bottom		
2	Flange for reservoir connection with outlet tap	output flange in metal according to reservoir outlet, including shutter valve		

3	Water pipe DN 50	water pipe compatible with flange above to connect to the surface pump, can be sewage type, installation needs to cover all eventual misalignments or deviations from horizontal or vertical positioning of pumps and reservoirs		
4	Surface pump complete kit	Complete kit containing: - surface pump - surface pump controller - surface pump switch box - surface pump controller for AC grid connection as backup - 2x 330 Wp PV Modules, - MNPV3 combiner box - MC4 extension cable - top of pole solar panel mount - 40 steel pipe - grounding lugs - submersible pump cable - submersible pump water lifting pipe - water level switch - lightning arrestors		
5	Submersible pump complete kit	Complete kit containing:- submersible pump- submersible pump controller- submersible pump1 controller for AC grid connection as backup- 2x 330 Wp PV Modules,- MNPV3 combiner box- MC4 extension cable- top of pole solar panel mount- 40 steel pipe- grounding lugs- submersible pump cable- submersible pump water lifting pipe- water level switch- lightning arrestors		

7	Cast resin sleeve for submersible pump electric connection  Submersible cable to train	Pass 3 x 1,5 to 5 x 6mm², lateral 3 x 1,5 to 5 x 4mm², hardener 0,225kg, incl. sleeve, polyurethane cast-resin, hardener, gloves, two foam seals and abrasive paper Submersible cable		
	cast resin application			
8	Water pressure gauge	PRESSURE GAUGE WITH TEE 0-60PSIG, EA		
9	Closing valve	Ball valve with spring return DN40 - 1 1/2" inch GK13, brass		
10	Water flow meter	Range: 240 l/min, Pressure: min. 12 bar; temperature control; compatible with water pipe diameters (adapters must be supplied if device differs from piping), display with values in metric, IP65, supply voltage according to pump electrical specifications (power supply must be supplied if device cannot be powered from the pump controller)		
11	PV Modules Total min 300Wp, Voltage suitable for Charge Controller, Inverter AS REFERENCE FOR THE PV MODULES INCLUDED IN PUMP KITS ABOVE!	PV saline protection (IEC 61701) if location is close to the sea Nominal Power per PV Module min 300 W (when using multiple PV Modules they have to be the same manufacturer and model) Open Circuit Voltage (STC) max 42 VDC Bypass diodes min 3 Reverse Current min 15 A Voltage Capability min 1000 VDC IP Class Junction Box min		

12	Roof Mounting	IP65 Temperature Range - 4085°C Cell Efficiency min 18% Power Tolerance max 5% MC4 Compatible Connectors Monocrystalline or Polycrystalline Technology		
	Substructure, Aluminium for Metal sheet Roof with wooden Screws			
	for wooden substructure on a training rood			
	Solar water pumping			
13	indoor 500700 W Solar Water			
	Pumping System (made up of the following components)	set, complete mounting board with pre-installed material as noted below for complete turn-key installation and additional consumables (e.g., wires, fuses, battery fuses, combiner and distribution boxes, load centre, earthing system, surge protection devices, etc.) All components shall be pre-installed on a mounting board covering electrical components and consumables. PV modules and batteries are not part of the mounting board, but their cabling and connection must be designed for plug and play usage.  lump sum, turn-key installation at site by a qualified technician Documentation for all technical products shall		
14	Submersible pump system	be available Submersible Pump,		
	(will be inserted into reservoir)	range 500700 W Complete submersible		

		pump kit - DC submersible water pump - DC submersible water pump controller - submersible cable for electrical connection - flexible water pipes of sufficient length (installation set)  Pump has to be attached to the mounting board at the lowest point with no electrical components below. Electronic equipment has to be protected from accidental water pipe bursts by using transparent shielding. Pumping Head max 15 m Flow Rate min 15 m³/h Water Pipe Length, 2 pcs, min 30 m, One for each reservoir. Reservoirs will be installed outside the building for safety reasons. Connection has to be pluggable without tools for setup and removal. Dry Run Protection Sensor. Has to be		
		removal. Dry Run Protection		
15	Safety water level sensor			
16	for safety water reservoirs  DC bench power supply (to	voltage and current		
	simulate PV modules)	specifications according to both pumps;at least 2 channels; adjustable 0 - 30 VDC; 0 - 3A; 195W;Resolution: Voltage: ≤0.01% + 2mV; Current: ≤0.01% + 250uA		

17	Surface Pump (wall mount on mobile work bench)	complete surface pump kit - DC surface water pump - DC surface water pump controller - flexible water pipes of sufficient length (installation set) - 2 water level sensors (high/low) - dry running protection		
18	Surface Pump Control Unit (wall mount on mobile work bench)	only for reference (must be included in surface pump kit)		
19	Surface Pump tubes, pipes, sensors	only for reference (must be included in surface pump kit)		
20	Water pressure gauge	according to used water pipes		
21	Water reservoir	200 litres with cover		
22	Safety water reservoir (water reservoir will stand inside)	PE, must be able to take up all the water from both reservoirs plus safety (volume of one reservoir)		
23	Mobile work bench	including RCD with 6 AC outlets, electrically safe and acid resistive coating, dimensions: 1250 x 1970 x 700 mm		
24	Acrylic safety housing for surface pump	dimensions must match the surface pump		
25	Emergency stop switch for pumps	red emergency stop button on yellow background, surface mounted		
26	Relay box with 4mm laboratory safety connectors	plastic box with DIN rail mount to hold 3 relays - 6 red 4mm terminals (32 A rated) with 2.5mm² cable connections to 3 relays - 6 black 4mm terminals (32 A rated) with 2.5mm² cable connections to 3 relays		

27	Work board (to be attached to the mobile work bench)	dimensions must match and fit to the mobile work bench, e.g. 1250 x 1000 mm; 20 mm thickness		
G	TESTING EQUIPMENT			
	Tools for testing			
	IV-Curve tracer - HT I- V500W	Testing Equipment: IV- Curve Tracer; Isolation tester, Camera, EL- Camera (Electroluminescence), Thermography camera,		
1		laboratory power supply		
2	Isolation measurement equipment/installation tester	Benning PV 1-1 Installations tester kalibriert (ISO) VDE- Norm 0126		
	Thermography camera	Image quality with IR		
		resolution of minimum 320 x 240 pixels (with testo SuperResolution technology 640 x 480		
3		pixels)		
4	Camera	Technical specifications: Min. 12 MP		
	Electroluminescence camera	Modified Consumer Camera (preferred SLR Camera from Sony: Sony		
5		Alpha 7a)		
6	IR thermometer	Fluke 62 MAX Infrarot- Thermometer Optik 10:1		
7	Multimeter x2	Fluke 289 FlukeView® Forms Combo Kit	 	
	Pressure valve	Flux 0.4-10 m <sup>3</sup> /h,	 	
8	·	regulate flow rate		
9	Flow meter	Min. 0.4 m³/h - 10 m³/h/ Digital output via USB		
	Technical testing equipment			
	Laboratory power supply	Technical specifications:		
10	x2	15A, 60V		
11	PV modules testing stand	2 PV modules + alum. structure/rack (other already included in and "Tools")		

12	Small inverters testing stand	Just price for small inverters, as this can be included in modules			
		testing setup and "Tools"			
	Test Stand Charge	Included in stand-			
	Controller	alone/SHS rig and			
13		"Tools"			
	Test Stand Batteries	Included in stand-			
		alone/SHS rig and "Tools" + lead-acid			
14		battery and 4-			
		Quadranten PV power			
		supply kit			
	Stand-alone/Solar-home-	Costs mainly for building			
4-	systems testing kit	up the rig: akku, micro-			
15	,	inverter, bulbs and small			
		electronic devices			
	PV water pumping testing	As part of the Water			
	stand	Pumping outdoor			
16		training unit			
	Cable and connectors	"Tools" should be			
17	testing kit	enough + prices for some			
		cables (as sample)			
	Lighting	For this one the testing			
18		and training rig would be the same			
10	Material (tools, racking,	the same			
	test stand setup, pipes,				
19	cable, safety equipment,				
	spare parts)				
20	Microinverter x5				
21	Bulbs				
22	Computer/office x2				
	· ·	Grand Total (\$)	<u> </u>	I	

- ISA will evaluate the financial offers received from the bidders based on total quoted price excluding tax.
- # Please provide details of the nature of the taxes. Taxes will be paid on actual basis on submission of documents proving the nature and the amount of tax.
- \* ISA reserves the rights to select/deselect items from list of equipment's.

SL NO.	BRIEF DESCRIPTION OF GOODS/ SERIVCES	Price in USD	Customs duty/excise duty/other taxes#
1	Component A: Supply of required solar equipment's* (As detailed out above) and Installation & Commissioning		
2	Component B: Training Charges		
3	Component C: Comprehensive maintenance of the system for the period of one year form the date of commissioning.		
	Total Price		
	Transportation Price (up to delivery site)		
	Insurance Price (up to delivery site)		
	Other Charges (specify)		
	Total Final and All-inclusive Price		

## **Compliance with Requirements**

You Responses		
Yes, we will comply	No, we cannot	If you cannot comply, pls. indicate counter - offer
	comply	

Minimum Technical Specifications		Click or tap here to enter text.
Delivery Term (INCOTERMS)		Click or tap here to enter text.
Delivery Lead Time		Click or tap here to enter text.
Warranty and After-Sales Requirements		Click or tap here to enter text.
Validity of Quotation		Click or tap here to enter text.
Payment terms		Click or tap here to enter text.
Other requirements [pls. specify]		Click or tap here to enter text.

## Other Information:

Estimated weight/volume/dimension of the	Click or tap here to enter text.
Consignment:	
Country/ies of Origin:	Click or tap here to enter text.
(if export licence required this must be submitted	
if awarded the contract)	

I, the undersigned, certify that I am duly authorized to sign this quotation and bind the company below in event that the quotation is accepted.			
Exact name and address of company  Authorized Signature:			
Company NameClick or tap here to enter text.	Date:Click or tap here to enter text.		
Address: Click or tap here to enter text.	Name:Click or tap here to enter text.		
Click or tap here to enter text.	Functional Title of Authorised		
Phone No.:Click or tap here to enter text.	Signatory:Click or tap here to enter text.		
Email Address:Click or tap here to enter text.	Email Address: Click or tap here to enter text.		

## ANNEX 5: CHECKLIST FOR SUBMISSION OF BID

Item	Yes, we have submitted	If you cannot submit, pls. indicate the reason
Technical Proposal		Click or tap here to enter text.
Filled up Annex 2 and Bidder Declaration form		
Registration Certificate		
Annual Turnover Certificate		
Documents against Qualifying criteria as per Annexure-3		
Financial Proposal		Click or tap here to enter text.
Quoted prices for all items in the list		
Quoted prices for Transportation (up to the delivery site)		
Quoted prices for Insurance (up to the delivery site)		
Quoted prices for VAT or other taxes and duties		

The submission of proposal should highlight in subject line "STC for equipment in Somalia"